

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Carmella Adams
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN
Register of Deeds Stamp & File Number

Table with columns: MACOMB (County), Located In: Chesterfield Township, Corner Code # A-13, and numbered rows 1-5 for Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec., Lot No., and Private Claims.

Grid table with columns A-M and rows 2-13, containing numbers 6 through 36.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules...

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: GLO POST, NO WITNESSES REMAIN; MACOMB COUNTY ROAD COMMISSION (1934); MACOMB COUNTY ROAD COMMISSION (1957); LCRC (1980); CLINTON TOWNSHIP / CONTROLLING IN SECTION 1, T.2N., R.13E.; LCRC (1989); HARRISON TOWNSHIP / CONTROLLING IN SECTION 6, T.2N., R.14E.; LCRC (1989); CLINTON TOWNSHIP / CONTROLLING IN SECTION 1, T.2N., R.13E.; LCRC (1989); CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T.3N., R.14E.; LCRC (1989); CHESTERFIELD TOWNSHIP / CONTROLLING IN SECTION 31, T.3N., R.14E.; LCRC (1989); CLINTON TOWNSHIP / CONTROLLING IN SECTION 1, T.2N., R.13E.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1" PIPE

THIS CORNER VERIFIED BY: M.D.O.T. RIGHT-OF-WAY DRAWING SHEET 138; MATCHES EDESEL FORD - ROSSO SUBDIVISION LIBER 38 PAGE 13

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DoDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- REPLACED 1" PIPE WITH 3/4" BAR MACOMB COUNTY REMONUMENTATION MARKER #30092
WITNESSES: N 05° E 40.96' FOUND POINT "x" ANGLE IRON FENCE POST IN CONCRETE; N 40° W 19.59' FOUND PK NAIL IN THE NORTHEAST FACE OF A 4" BASSWOOD TREE; EAST 7.50' FOUND 3/4" PIPE; SOUTH 60.34' FOUND PK NAIL IN THE NORTH EDGE OF ROSSO HIGHWAY; EAST 125.86' FOUND CENTERLINE OF SNOVER ROAD PAVEMENT

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature] Date 12-15-93

Surveyor's Michigan License No. 30092