

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

Located In: Chesterfield Township Corner Code # B-9

Table with 5 rows and 4 columns: Survey Type, T, R, and Corner Code. Row 1: Public Land Survey, T 3N, R 14E, B-9. Row 2: Property Controlling in Section, S, T, R. Row 3: Miscellaneous Property in Sec., S, T, R.

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk - Register of Deeds, Macomb County, Michigan.

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST. NO WITNESSES REMAIN

LCRC (1977) L. 2862 P. 854 STONEROCK #13601
SET RAILROAD SPIKE WITH CUT "X"
N 77° 45' 20" W 71.60' PK SOUTH FACE POWER POLE
S 34° 12' 40" E 75.38' NE CRNR CONC BLOCK FND N
S 01° 14' 20" E 28.59' NAIL/TIN W FACE 14" MAPLE
S 47° 32' W 98.79' NW CRNR CONC BLOCK FND N

LCRC (1988) L. 4487 P. 201 GORMAN #17622
FOUND R/8" REROD 8" BELOW SURFACE
S 05° W 28.06' 25" MAPLE
N 80° W 73.25' POWER POLE
NORTH 39.09' 11" CATALPA
N 75° E 88.06' POWER POLE

LCRC (1979) L. 3055 P. 820 SWITH #16052
FOUND 5/8" IRON 10" DEEP / SET 1" ROD ON TOP
SOUTH 28.00' PK IN 15" MAPLE
N 80° E 88.10' PK IN POWER POLE
N 75° W 73.25' PK IN POWER POLE
** (FOUND RAILROAD SPIKE 0.40' NORTH AND 1.60' WEST OF TRUE CORNER)

LCRC (1990) L. 4490 P. 164 STEVEDANN #28408
FOUND PK NAIL
EAST 1.63' FOUND 1. ROD IN MONUMENT BOX
S 35° E 75.38' NE CRNR CONC BLOCK FOUNDATION
SOUTH 28.44' NAIL/WASHER WEST SIDE 18" MAPLE

LCRC (1991) L. 5024 P. 940 DeDECKER #6386
FOUND PK NAIL
AZ EAST 1.63' FOUND 5/8" ROD IN MONUMENT BOX
AZ 81° 87.98' PK W/SDA TAG IN NW FACE U.P.
AZ 151° 75.42' NE CORNER OF PSE #26000, CONC BLK
AZ 183° 28.43' NAIL W/MDOT TAG W FACE 30" MAPLE
AZ 223° 54.87' PK W/SDA TAG SE FACE 12" MAPLE
AZ SOUTH 13.64' FND 1/2" IRON ROD @ EDGE ASPHALT

Grid table with columns A-M and rows 2-13. A dot is marked at row 9, column C.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-9 FOUND IRON IN MONUMENT BOX
FOUND PK NAIL 1.63' WEST AND SLIGHTLY NORTH OF IRON IN MONUMENT BOX

PK NAIL IS CORRECT CORNER
THIS CORNER VERIFIED BY:
CERTIFICATE OF SURVEY LIBER 3057 PAGE 155
SUPERVISOR'S PLAT OF FRASERS PATTON ROAD PLACE SUBDIVISION LIBER 23 PAGE 36

FOUND RAILROAD SPIKE BELOW PK NAIL

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-9 REMOVE PK NAIL AND RAILROAD SPIKE AND REPLACE WITH 3/4" BAR AND MACOMB REMONUMENTATION MARKER #30092 IN MONUMENT BOX
WITNESSES:
S 30° W 75.42' FOUND NORTHEAST CORNER OF CONCRETE BLOCK AT HOUSE #26000
S 05° W 28.43' FOUND NAIL W/MDOT TAG IN WEST FACE OF A 30" MAPLE TREE
S 55° W 54.87' FOUND PK NAIL W/SDA TAG IN THE SOUTHEAST FACE OF A 12" MAPLE TREE
SOUTH 13.64' FOUND 1/2" REBAR JUST SOUTH OF THE EDGE OF PAVEMENT
S 45° W 98.79' FOUND NORTHWEST CORNER OF CONCRETE BLOCK FOUNDATION

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Shelby W. Money Date 12/19/93
Surveyor's Michigan License No. 30092

Vertical stamp: ACCEPTED BY THE MACOMB COUNTY SURVEY PIER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 1990 AT A MEETING HELD ON 12-15-93. Signature of Frank J. DeDecker, FS, PE, Chairman. Circular seal: SHELBY W. MONEY PROFESSIONAL SURVEYOR No. 30092 LICENSED PROFESSIONAL SURVEYOR