

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 AM

DEC 28 1993

Carmela [Signature] CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

Table with columns: (County) MACOMB, Located In: Chesterfield Township, Corner Code: C-8. Rows include Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

Grid table with columns A-M and rows 2-13. Cell (8,20) contains a dot.

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST, NO WITNESSES REMAIN

LCRC (1973) L.2433 P.39 SMITH #16052
FOUND IRON
SOUTHWEST 30.25' SOUTHEASTERLY CORNER OF FRAME BARN
SOUTHEAST 3.15' CORNER OF THE OLD FOUNDATION
SOUTHEAST 67.73' NORTHWESTERLY CORNER OF GARAGE

LCRC (1990) L.4990 P.166 STEVE DUNN #30081
FOUND 1/2" IRON ROD
NORTH 3.20' SOUTH EDGE OF CONCRETE PAVEMENT
ENE 2.08' WEST FACE OF STEEL OF FENCE CORNER POST
SOUTHWEST 16.70' NORTHEAST CORNER CONCRETE FOUNDATION OF BARN
EAST 11.90' FIRST STEEL FENCE POST EAST OF STEEL CORNER POST

LCRC (1991) L.5024 P.935 DeDECKER #8386
FOUND 1/2" IRON ROD
AZ 25° 57.97' PK W/SDA TAG IN CONCRETE PAVEMENT @ CORNER OF BUILDING #50002
AZ 170° 8.63' PK W/SDA TAG IN THE EAST FACE OF TRIPLE 14" TREES
AZ 276° 17.15' PK W/SDA TAG IN THE NORTH FACE OF 10" TREE
AZ 325° 69.42' PK W/SDA TAG IN SOUTHWEST CORNER OF CONCRETE PAD FOR DE TRANSFORMER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-8 FOUND 1/2" REBAR IN GOOD CONDITION

THIS CORNER VERIFIED BY:
FOUND MOST WITNESSES
CERTIFICATE OF SURVEY LIBER 2433 PAGE 37-38
CERTIFICATE OF SURVEY LIBER 3461 PAGE 307

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-8 REMOVE 1/2" REBAR AND REPLACED WITH A 3/4" BAR WITH MACOMB COUNTY REMONUMENTATION MARKER #39002
WITNESSES FROM LIBER 5024 PAGE 935:
AZ 25° 57.97' FOUND PK W/SDA TAG IN CONCRETE PAVEMENT @ CORNER OF BUILDING #50002
AZ 170° 8.63' FOUND PK W/SDA TAG IN THE EAST FACE OF TRIPLE 14" TREES
AZ 276° 17.15' FOUND PK W/SDA TAG IN THE NORTH FACE OF 10" TREE
AZ 325° 69.42' FOUND PK W/SDA TAG IN SOUTHWEST CORNER OF CONCRETE PAD FOR DE TRANSFORMER

The selected location is accepted by me and is generally accepted by Professional Surveyor as the best available evidence of the position of the original corner.

Signed by [Signature] Date 12/14/93
Surveyor's Michigan License No. 30092

