

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB (County)

Located In: Chesterfield Township Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3N R 14E C-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. Recorded Plat
5. Private Claims

I, Shelby W. Money, in a field survey on November 18, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at row 11, column B.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST, NO WITNESSES REMAIN

MACOMB COUNTY ROAD COMMISSION (1959) UNRECORDED
FOUND 1/2" PIPE
S 58' W 45.89' POWER POLE
N 12' W 57.85' POWER POLE
N 36' E 29.56' A CHISELED "+" CROSS AT THE NORTHWEST CORNER OF CAST CULVERT HEADWALL

LCRC (1979) L.3055 P.838 AVENDT #75034
SET IRON
NORTH 00.28' SOUTH EDGE OF TWENTY ONE MILE ROAD CONCRETE PAVEMENT
SOUTHWEST 77.30' NAIL AND CAP IN THE SOUTHEAST CORNER OF WOOD GUARD POST
WEST/NORTHWEST 2.83' CHISELED "+" CROSS IN PAVEMENT (FOUND)
EAST/NORTHEAST 3.29' CHISELED "+" CROSS IN PAVEMENT (FOUND)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-11 FOUND 1/2" REBAR WITH CAP #30103 / ROGER STECKER

THIS CORNER VERIFIED BY:

- KLUMPP SUBDIVISION LIBER 33 PAGE 14
INDUSTRIAL PARK 21 SUBDIVISION LIBER 86 PAGE 23
INDUSTRIAL PARK 21-2 SUBDIVISION LIBER 89 PAGE 35
M.D.O.T. RIGHT-OF-WAY DRAWING SHEET 138

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
Signature: Frank J. Dedecker, PE, Chairman

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-11 REPLACED 1/2" REBAR AND CAP #30103, WITH 3/4" BAR AND MACOMB COUNTY REMONUMENTATION MARKER #30092
WITNESSES:
NORTH 0.28' FOUND SOUTH EDGE OF TWENTY ONE MILE ROAD CONCRETE PAVEMENT
WEST/NORTHWEST 2.83' FOUND CHISELED "+" CROSS IN PAVEMENT
EAST/NORTHEAST 3.29' FOUND CHISELED "+" CROSS IN PAVEMENT
SOUTHWEST 79.20' SET PK W/MCW TAG IN THE TOP OF MOST EASTERLY GUARDRAIL POST ON THE SOUTH SIDE OF RAMP

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Shelby W. Money Date 12/4/93
Surveyor's Michigan License No. 30092

