

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

MAR 17 2000

For corners in

CHESTERFIELD TOWNSHIP  
Located In:

MACOMB

Corner Code #

(County)

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>3N</u> R <u>14E</u> | <u>D-1</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/5/99  
*William E. Soeberberg*  
WILLIAM E. SOEBERBERG, P.S., CHAIRMAN

SECTION

1091808  
LIBER 9267 PAGE 965  
12/27/1999 01:14:43 P.M.  
MACOMB COUNTY, MI  
CARNELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Num

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, ROBERT BIRKETT, in a field survey on JULY 10, 19 99 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- D-1 CHESTERFIELD  
1817, W. PRESTON, GLO, SET POST  
a) 1973, G. AVENDT # 16034, SET 1" IRON FROM NOTES OF CHARLES SCHAACH, SURVEY, L.2383, P. 858, MRC.  
b) 1973, G. AVENDT # 16034, SET 1" IRON FROM NOTES OF CHARLES SCHAACH, LCRC, L.2383, P. 863, MRC.  
c) 1975, R. SMITH #16052, 1" IRON PIPE, SURVEY, L.2578, P. 279, MRC.  
d) 1976, R. SMITH # 16052, 1" IRON ROD, SURVEY, L.2715, P. 767, MRC.  
e) 1988, W. AVEY # 30076, 1" IRON BAR, LCRC, L.4353, P. 427, MRC.  
f) 1993, R. SMITH # 16052, PIN IN HAND HOLE, SURVEY, L.6054, P. 462, MRC.  
g) NO DATE, J. NEIDERHAUSER # 24608, IRON BAR, JAMES LAND SURVEYING RECORDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-1 CHESTERFIELD, FOUND 1" IRON IN CENTER ASPHALT ROAD (26 MILE) IN HAND HOLE, 0.59' SOUTH OF SECTION LINE.

SEE BACK

FIELD MEASUREMENTS

(SEE SKETCH ON BACK)

D-1 TO C-1 CHESTERFIELD	D-1 TO E-1 CHESTERFIELD	D-1 TO C-13 LENOX	D-1 TO D-13 LENOX
GLO (1817) - 40 CHAINS (2640')	GLO (1817) - 40 CHAINS (2640')	GLO (NONE)	GLO (NONE)
G. AVENDT (1973) - 2713.54'	J. NIEDERHAUSER (NO DATE) - 2714.44	RE-MON. (1999) - 486.15'	RE-MON. (1999) - 2243.47'
RE-MON. (1999) - 2715.00'	RE-MON. (1999) - 2714.20'		

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 CHESTERFIELD

SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, MI ACT 345, #41094, D-1" IN NEW MONUMENT BOX, 0.52' NORTH OF FOUND 1" IRON ON LINE BETWEEN C-13, D-13 LENOX TOWNSHIP. T4N, R14

- AZ. 175° 107.95' - NORTHWEST CORNER BRICK HOUSE #28000 26 MILE ROAD
- AZ. 180° 48.89' - SET REMON. TAG IN WEST FACE 18" WILD CHERRY TREE.
- AZ. 195° 33.46' - FOUND 1/2" IRON.
- AZ. 230° 42.75' - FOUND A PK NAIL WITH TAG #19837 IN NORTHEAST FACE OF A 24" OAK.
- AZ. 255° 66.53' - FOUND A NAIL WITH CAP #24608 IN NORTH NORTHWEST FACE OF A 48" OAK.
- AZ. 310° 61.61' - FOUND 1/2" IRON #30103.
- AZ. 350° 32.41' - FOUND FORM NAIL WITH CAP #5187 IN WEST FACE OF A UTILITY POLE.



Signed by Robert H. Birkett Date NOVEMBER 23, 1999  
Surveyor's Michigan License No. 41094

SURVEY &  
REMONUMENTATION

MAR 17 2000

LIBER 9267 PAGE 966

SECTION

MACOMB COUNTY  
CHESTERFIELD TOWNSHIP  
TOWN 3 NORTH, RANGE 14 EAST

PART B CONTINUED FROM FRONT

D-1 CHESTERFIELD, FOUND 1" IRON IN CENTER ASPHALT ROAD (26 MILE) IN HAND HOLE, 0.59' SOUTH OF SECTION LINE.  
NORTH - (a, b, c, e 33.00') (D 32.95') - NAIL & CAP IN SERVICE POLE.  
SSE - (a, b, c, e 33.00') - FOUND 1/2" IRON.  
SOUTH - (D 48.37') - pk nail in 15" cherry.  
SW - (a, b, c, e 66.31') - NAIL & CAP NW SIDE 48" OAK.  
Nw - (e 61.30') - 1/2" iron #30103.

