

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

C104894

94 AUG -5 PM 1:41

CARMELLA SABAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

LIBER 06415PG471

Register of Deeds Stamp & File Number

For corners in

**MACOMB**

(County)

Located In:  
**CHESTERFIELD**

Corner Code #

- |                                    |                          |            |
|------------------------------------|--------------------------|------------|
| 1. Public Land Survey              | T <u>3N</u> R <u>14E</u> | <u>D-5</u> |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
|                                    | T _____ R _____          | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____      |
|                                    | S _____ T _____ R _____  | _____      |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on APRIL 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND  
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

L.C.R.C.

- |                |  |
|----------------|--|
| L. 2898 P. 522 | ROBERT L. SMITH, #16052, FOUND 1/2" IRON ROD, JANUARY 4, 1978        |
| L. 4105 P. 602 | RAYMOND J. DONNELLY, #21563, FOUND 1/2" IRON ROD, JANUARY 8, 1987    |
| L. 4723 P. 618 | RAYMOND J. DONNELLY, #21563, FOUND 1/2" IRON ROD, SEPTEMBER 15, 1989 |

**ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 946 OF 1988 AT A MEETING HELD ON 6-21-94**

*William E. Sodeberg*  
**WILLIAM E. SODEBERG, P.S., CHAIRMAN**

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-5 1/4 CORNER

FOUND 1/2" IRON ROD IN GRAVEL ROAD, VERIFIED LOCATION BY CHECKING EXISTING WITNESS OF ABOVE  
WEST TO SECTION CORNER - 2740.54' M  
EAST TO SECTION CORNER - 2716.33' M

- |                |  |
|----------------|--|
| L. 2898 P. 522 | N.80°E. PK. NAIL IN NORTHWEST SIDE OF UTILITY POLE<br>NORTH 50.00 CONCRETE MONUMENT          |
| L. 4105 P. 602 | N.05°E. 50.00 CONCRETE MONUMENT<br>N.85°E. 178.93 PK. NAIL IN NORTHWEST FACE OF UTILITY POLE |
| L. 4723 P. 618 | N.05°E. 50.00 CONCRETE MONUMENT<br>N.85°E. 178.93 PK. NAIL IN NORTHWEST FACE OF UTILITY POLE |

REPLACED WITH MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-5 T.3N., R.14E. MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD IN GRAVEL ROAD.

WITNESSES

- |                 |   |
|-----------------|---|
| NORTH 50.00     | FOUND CONCRETE MONUMENT.  |
| S.38°W. 106.58' | SET P.K. NAIL IN TWIN 10" ELM.  |
| N.80°E. 178.72' | FOUND P.K. NAIL IN NORTH WEST FACE OF UTILITY POLE.                                     |
| S.87°W. 286.38' | FOUND P.K. NAIL IN ASPHALT PAVEMENT ±10' EAST OF RAILROAD TRACK ON SOUTH SIDE PAVEMENT. |

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

Signed by Steven E. Dunn Date July 22, 1994  
Surveyor's Michigan License No. 28408