

MAR 17 2000

SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

1091809
LIBER 9267 PAGE 967
12/27/1999 01:14:47 P.M.
MACOMB COUNTY, MI
CARHELLA SABAUGH, REG/DEEDS

For corners in

MACOMB
(County)

CHESTERFIELD TOWNSHIP
Located In: Corner Code #

- | | | | |
|------------------------------------|-------|---------------------|------------|
| 1. Public Land Survey | | <u>T 3 N R 14 E</u> | <u>E-1</u> |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| | | T ___ R ___ | _____ |
| 2. Property Controlling in Section | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |
| 3. Miscellaneous Property in Sec. | S ___ | T ___ R ___ | _____ |
| | S ___ | T ___ R ___ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT H. BIRKETT, in a field survey on JULY 10, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

**A. Description of original monument and accessories and/or subsequent restoration:
E-1 CHESTERFIELD**

- 1818, W. PRESTON, GLO, SET POST
- (a) 1973, R. SMITH #16052, 1/2" IRON IN MON. BOX, SURVEY L. 2578, P. 279 M.C.R.
 - (b) 1973, R. SMITH #16052, 1/2" IRON IN MON. BOX, L.C.R.C., L. 2578, P. 280 M.C.R.
 - (c) 1989, C. DeWINTER #25839, 1/2" IRON IN MON. BOX, SURVEY, L. 4650, P. 401, M.C.R.
 - (d) 1993, D. KING #30085, 1/2" IRON IN MON. BOX, SURVEY, L. 6595, P. 744 M.C.R.
 - (e) 1993, D. KING #30085, 1/2" IRON IN MON. BOX, L.C.R.C. 6586, P. 191 M.C.R.
 - (f) 1997, D. KING #30085, 1/2" IRON IN MON. BOX, SURVEY L. 8044, P. 901 M.C.R.
 - (g) 1997, J. WRIGHT #40165, 1/2" BAR IN MON. BOX, L.C.R.C. L. 7912, P. 851 M.C.R.
 - (h) NO DATE, J. NIEDERHAUSER #24608, IRON BAR, JAMES LAND SURVEYING RECORDS.

ACCEPTED BY THE MACOMB COUNTY SURVEY GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING ON 10/15/99
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
E-1 CHESTERFIELD. FOUND 1/2" IRON IN MONUMENT BOX, CENTER ASPHALT 26 MILE ROAD.**

SEE BACK

FIELD MEASUREMENTS (SEE SKETCH ON BACK)

E-1 TO D-1 CHESTERFIELD	E-1 TO F-1 CHESTERFIELD	E-1 TO D-13 LENOX	E-1 TO E-13 LENOX
GLO (1817) - 40 CHAINS (2640')	GLO (1817) - 40 CHAINS (2640')	GLO (NONE)	GLO (NONE)
J. NIEDERHAUSER - 2714.44'	NO PRIOR DISTANCES RECORDED	RE-MON. (1999) - 470.73'	RE-MON. (1999) - 2255.28'
RE-MON. (1999) - 2714.20'	RE-MONUMENTATION (1999) - 2676.47'		

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-1 CHESTERFIELD.**

SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, M1 ACT 345, #41094, E-1" EXISTING MONUMENT BOX ON LINE BETWEEN D-13 AND E-13, LENOX TOWNSHIP T4N,R14E.

- AZ 20° 32.29' - FOUND NAIL WITH M.C.R.C. TAG IN THE EAST FACE OF A UTILITY POLE.
- AZ 80° 125.09' - SET REMON. TAG IN THE SOUTHEAST FACE OF A NEW UTILITY POLE.
- AZ 120° 90.96' - SET REMON. TAG ABOVE FOUND P.K. NAIL IN THE NORTHEAST FACE OF A TELEPHONE POLE.
- AZ 260° 116.29' - SET REMON. TAG ABOVE FOUND SPIKE IN THE NORTH FACE OF A TELEPHONE POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Robert H. Birkett Date NOVEMBER 23, 1999
Surveyor's Michigan License No. 41094

94

917

SURVEY &
REMONUMENTATION

MAR 17 2000

LIBER 9267 PAGE 968

SECTION

MACOMB COUNTY
CHESTERFIELD TOWNSHIP
TOWN 3 NORTH, RANGE 14 EAST

PART B CONTINUED FROM FRONT

E-1 CHESTERFIELD - FOUND 1/2" IRON IN MONUMENT BOX CENTER ASPHALT 26 MILE ROAD, ON SECTION LINE.

NNE - (a, b, 32.30') (d, e, f 32.28') (g 32.26') - M.C.R.C. TAG IN POWER POLE

SE - (d, e, f 91.05') (g 90.93') - PK NAIL IN D.E. POLE

