

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Chesterfield

Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30A M.

DEC 28 1993

Clerk - Register of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 14 E E-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 5, column D.

I, Steven E. Dunn, in a field survey on December 4, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GL0 Post - No evidence of original corner found.

GL0 Original survey performed by Preston 2-18-1818.

L.C.R.C.: L.2474, P.633 Robert L. Smith #16052 February 13, 1974
L.4105, P.603 Raymond J. Donnelly #21563 January 8, 1987
L.4723, P.605 Raymond J. Donnelly #21563 September 15, 1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-5 Found 1/2" Iron Rod in monument box.

Found corner matches corner described in above L.C.R.C's and found witnesses.

Replaced with Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DECKER, PS, PE CHAIRMAN



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-5, T.3N.,R.14E.

Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod in monument box.

Witnesses:

- S.02°E. - 30.87' Found PK nail w/MCRC tag in East face utility pole.
N.01°E. - 31.15' Found 1/2" Iron Rod w/trav. cap # 30092.
N.51°W. - 49.20' Found PK nail w/RJD flasher in NE face utility pole.
S.03°W. - 48.15' Set PK nail w/Macomb Co. witness tag in West face 28" poplar.
N.67°E. - 82.40' Found PK nail in SE face utility pole.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn

Date 12-20-93

Surveyor's Michigan License No. 28408