

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

Macomb (County)

Located In:

Corner Code #

Chesterfield

DEC 28 1993

- 1. Public Land Survey T 3 N R 14 E E-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Carmella A. ... CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. ... Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 6, column D.

I, Steven E. Dunn, in a field survey on December 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Post - No evidence of original corner found.

GLO Original survey performed by Preston 2-18-1818.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-6 Found 2 1/2" Iron Pipe Verified location by comparing distances to found iron on E-W 1/4 line and to NW section corner. Also compared with copy of Giffels-Webster field notes for corner and witnesses. They call for 3/4" pipe but South witness matches and East witness matches by 0.30'.

Placed Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod inside 2 1/2" iron pipe

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. Frank J. DeDecker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 T.3N.,R.14E.

Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod inside 2 1/2" iron pipe.

Witnesses:

- N.70°W. - 72.27' Set 1/2" iron rod with traverse cap # 28408
N.53°E. - 4.20' Set scribed "+" on SW corner concrete pad for telephone box.
S.02°W. - 10.00' Found PK nail and GW tag # 78728 in East side 13" Cherry.
S.77°E. - 22.20' Found PK nail and GW tag # 78729 in South face utility pole.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn Date 12-22-1993

Surveyor's Michigan License No. 28408