

**SURVEY &  
REMONUMENTATION**

APR 28 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**C104996**

For corners in

<u>MACOMB</u> (County)	Located In: <u>CHESTERFIELD</u>	Corner Code # <u>E-7</u>
1. Public Land Survey	<u>T3N R14E</u>	<u>E-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER **06415PG473**  
94 AUG -5 PM 1:41  
CARMELLA TABAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI  
Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on APRIL 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
**GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND**  
**GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818**

- L.C.R.C.  
L. 3203 P. 359 - MYRON L. PETRIE, #19841, FOUND 3/4" IRON ROD IN MONUMENT BOX, JANUARY 22, 1980  
L. 3945 P. 712 - WARREN C. AVEY, #30076, FOUND 3/4" BAR IN MONUMENT BOX, MAY 19, 1986  
L. 4723 P. 619 - RAYMOND J. DONNELLY, #21563, FOUND 1" IRON ROD IN MONUMENT BOX, SEPTEMBER 15, 1989  
L. 5014 P. 015 - WARREN C. AVEY, #30076, FOUND 1" BAR IN MONUMENT BOX, DECEMBER 19, 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

**E-7 SECTION CORNER**  
**FOUND 1" IRON ROD IN MONUMENT BOX IN CONC. PAVEMENT.**  
**VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE L.C.R.C.'s AND COMPARED M-DOT DISTANCES ON M-29 RIGHT-OF-WAY MAPS EAST TO 1/4 CORNER.**  
L. 3945 P.712 NE 83.10' - CHISELED + ON TOP OF CURB AT P.T.  
SE 147.41' - C/L TOP OF FIRE HYDRANT  
L. 3203 P. 359 N.60°E. 83.12' - CHISELED X ON CURB AT P.T.  
S.05°E. 147.38' - TOP OF FIRE HYDRANT  
L. 5014 P. 015 NW 50.67' - CHISELED + IN NORTH RIM OF MBT MANHOLE  
SSE 147.36' - + IN TOP OF HYDRANT  
DISTANCE FROM E-7 TO D-7 = 2759.09'  
DISTANCE FROM E-7 TO F-7 = 2719.55'  
DISTANCE FROM E-7 TO E-6 = 2699.93'

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1980 AT A MEETING HELD ON 6-21-94  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

REPLACED WITH MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7 T.3N., R.14E. MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT.  
**WITNESSES**  
N.60°E. 83.10' CHISELED "x" ON TOP OF CURB AT P.T.  
N.20°W. 50.70' CHISELED "x" ON NORTH EDGE M.B.T. MANHOLE  
S.65°W. 67.35' SET P.K. NAIL IN UTILITY POLE  
S.05°E. 147.31' CENTERLINE TOP OF FIRE HYDRANT



HE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

Signed by Steven E. Dunn Date July 22, 1994  
Surveyor's Michigan License No. 28408