

**SURVEY &  
REMONUMENTATION**

APR 28 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

C104397

For corners in

MACOMB

(County)

Located In:  
CHESTERFIELD

Corner Code #

118FR **06415PG474**

- |                                    |             |               |            |
|------------------------------------|-------------|---------------|------------|
| 1. Public Land Survey              | T <u>3N</u> | R <u>R14E</u> | <u>E-7</u> |
|                                    | T           | R             |            |
|                                    | T           | R             |            |
|                                    | T           | R             |            |
| 2. Property Controlling in Section | S           | T             | R          |
|                                    | S           | T             | R          |
| 3. Miscellaneous Property in Sec.  | S           | T             | R          |
|                                    | S           | T             | R          |

94 AUG -5 PM 1:42  
CARMELLA SABAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, STEVEN E. DUNN, in a field survey on APRIL 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

CERTIFICATE OF SURVEY

L. 2347 P. 451 - ROBERT L. SMITH, #16052, FOUND 1/2" IRON ROD IN MONUMENT BOX, NOVEMBER 28, 1972

L.C.R.C.

L. 2347 P. 457- ROBERT L. SMITH, #16052, FOUND 1/2" IRON ROD IN MONUMENT BOX, NOVEMBER 28, 1972

L. 3644 P. 543 - HERBERT G. AVEY, #15396, FOUND 1/2" BAR IN MONUMENT BOX, JUNE 28, 1994

L. 4723 P. 619 - RAYMOND J. DONNELLY, #21563, FOUND 1/2" IRON ROD IN MONUMENT BOX, SEPTEMBER 15, 1989

L. 4810 P. 940 - JOHN R. FENN, #23505, FOUND 1/2" IRON IN MONUMENT BOX, FEBRUARY 5, 1990

L. 5014 P. 015 - WARREN C. AVEY, #30076, FOUND 1/2" BAR IN MONUMENT BOX, DECEMBER 19, 1990

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-7 1/4 CORNER

FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONC. PAVEMENT.

VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE L.C.R.C.'s AND COMPARED M-DOT DISTANCES TO THE SECTION CORNERS TO THE EAST AND WEST.

L. 3644 P. 543 45.67' NORTHEAST TO FORM NAIL IN WASHER #19397 IN SOUTH FACE OF POWER POLE

L. 4723 P. 619 AZ 52° 45.70' NAIL WITH TAG #19397 SOUTHEAST FACE OF UTILITY POLE

L. 4810 P. 940 SAME AS WITNESS IN SECTION C

L. 5014 P. 015 45.70' NORTHEAST TO FORM NAIL IN WASHER (#19397) IN SOUTH FACE OF POWER POLE

114.34' NORTHWEST TO PK. NAIL IN NORTH FACE OF UTILITY POLE

DISTANCE FROM F-7 TO E-7 = 2719.55'

DISTANCE FROM F-7 TO G-7 = 2719.93'

REPLACED WITH MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 T.3N., R.14E. MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT.

WITNESSES

N. 52°E. 45.70' FOUND SPIKE AND WASHER IN UTILITY POLE


NORTH 2.05' NORTH EDGE OF 23 MILE ROAD CONCRETE PAVEMENT.

N.67°W. 114.39' FOUND NAIL AND TAG #19397 IN SOUTH FACE OF UTILITY POLE.

N. 22°E. 95.68' FOUND NAIL AND TAG IN EAST FACE OF UTILITY POLE.

HE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

ACCEPTED BY THE MACOMB COUNTY SURVEY DEPT GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 246 OF 1980 AT A MEETING HELD ON 6-21-94  
*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by Steven E. Dunn  
28408  
Surveyor's Michigan License No. \_\_\_\_\_

Date July 22, 1994