

LIBER 08165 1972

B999605

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

For corners in

Macomb (County)

Located in: Chesterfield

Corner Code --#

- 1. Public Land Survey T 3 N R 14 E G-5
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

DEC 28 1993

Clerk - Register of Deeds MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 5, column G.

I, Steven E. Dunn, in a field survey on December 7, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Post - No Evidence of Original Corner.
GLO Original survey performed by Preston 2-18-1818.
Certificate of Survey: L.4055 P.615 Donald H. King #30085 October 27, 1986
L.C.R.C.'s L.3123 P.277 George J. Avenedt, Jr. #16034 July 3, 1979
L.3644 P.542 Hebert G. Avey #15396 June 28, 1984
L.4055 P.670 Donald H. King #30085 October 27, 1986
L.5290 P.287 Warren C. Avey #30076 January 6, 1992

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-5 No Corner Found. Corner may have been disturbed due to physical evidence of recent underground construction. Reset corner using found witnesses of above L.C.R.C.'s and comparing distances of above certificate of survey.

Set Macomb County Monument Marker #28408 on 3/4" x 24" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. Frank H. Decker, PS, PE, CHAIRMAN



C. Description of monument for corner and accessories:

- G-5 T.3N.,R.14 E.
Macomb County Monument Marker #28408 on 3/4" x 24" Iron Rod.
Witnesses:
N.49°E. - 34.23' Found notch in East end 60" C.M.P.
N.67°W. - 62.02' Found notch in West end 60" C.M.P.
N.36°W. - 45.56' Found P.K. Nail and Tag in West face Utility Pole.
S.40°W. - 40.79' Found P.K. Nail and Tag in West face Utility Pole.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn Date 12-20-93

Surveyor's Michigan License No. 28408