

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C150809

For corners in

LIBER **6523** PAGE **956**

94 DEC -9 PM 2:51

CAROL M. WADDAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

<u>MACOMB</u> (County)	Located In: <u>CHESTERFIELD</u>	Corner Code # <u>H-7</u>
1. Public Land Survey	<u>T 3N R 14E</u>	<u>H-7</u>
	<u>T R</u>	<u> </u>
	<u>T R</u>	<u> </u>
	<u>T R</u>	<u> </u>
2. Property Controlling in Section	<u>S T R</u>	<u> </u>
	<u>S T R</u>	<u> </u>
3. Miscellaneous Property in Sec.	<u>S T R</u>	<u> </u>
	<u>S T R</u>	<u> </u>
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1						
3												
4	7	8	8	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, STEVEN E. DUNN, in a field survey on APRIL 4, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-18-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

A. Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

<u>SKETCH OF SURVEY</u>			
L. 2336 P. 453-454	WILLIAM E. SODERBERG, #17635	FOUND 1/2" IRON ROD IN MONUMENT BOX	OCTOBER 20, 1972
L. 2547 P. 439	ROBERT L. SMITH, #16052	FOUND 1/2" IRON ROD IN MONUMENT BOX	NOVEMBER 6, 1974
L. 3123 P. 252	ROBERT L. SMITH, #16052	FOUND 1/2" IRON ROD IN MONUMENT BOX	JULY 3, 1979

<u>L.C.R.C.</u>	<u>NAME AND NUMBER</u>	<u>DESCRIPTION</u>	<u>DATE</u>
L. 2302 P. 914	GEORGE J. AVENDT JR. #16034	FOUND DOCK SPIKE IN MONUMENT BOX	JULY 7, 1972
L. 3168 P. 260	JOHN R. FENN, #23505	FOUND 3/8" IRON ROD IN MONUMENT BOX	OCTOBER 12, 1979

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-7 1/4 CORNER
FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT. VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE L.C.R.C.'s AND COMPARED M-DOT DISTANCES TO THE SECTION CORNERS TO THE EAST AND WEST.

FOUND WITNESS TIES
L. 3945, P. 715 N.W. 70.33' FOUND FORM NAIL IN MSHD DISK IN FACE OF UTILITY POLE
N.E. 134.58' FOUND FORM NAIL IN DISK IN SOUTHEAST FACE OF UTILITY POLE

FIELD MEASUREMENTS AND RECORDED DISTANCES
H-7 TO G-7 2719.03' (M.) G.L.O. 2645.94' (R.)
H-7 TO I-7 2714.42' (M.) G.L.O. 2640.00' (R.)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-7 T.3N., R.14E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN MONUMENT BOX.

WITNESSES
AZ. 165° 91.44' SET P.K. NAIL WITH M.C.R. TAG IN WEST FACE OF UTILITY POLE.
AZ. 0° 5.82' NORTH TO CONC. LINE NORTH EDGE OF 23 MILE ROAD
AZ. 80° 70.33' FOUND FORM NAIL IN MSHD DISK IN EAST FACE OF UTILITY POLE
AZ. 301° 134.58' FOUND FORM NAIL AND A PK IN SOUTHEAST FACE OF UTILITY POLE

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by Steven E. Dunn Date Nov. 22, 1994
Surveyor's Michigan License No. 28408