

**SURVEY &
REMONUMENTATION**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

94 DEC 14 AM 10:56
C152291
CASSAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

corners in **COMMISSION**

MACOMB (County) Located in: **CHESTERFIELD** Corner Code #

Public Land Survey T 3N R 14E I-4
 T ___ R ___
 T ___ R ___
 T ___ R ___

Property Controlling in Section S ___ T ___ R ___
 S ___ T ___ R ___

Miscellaneous S ___ T ___ R ___
 Property in Sec. S ___ T ___ R ___

LIBER 6527 PAGE 868

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	6	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

STEVEN E. DUNN, in a field survey on APRIL 5, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

L.C.R.C.	NAME AND NUMBER	DESCRIPTION	DATE
L.4687 P. 432	MARTIN C. DUNN, #30081	FOUND 1" IRON PIPE	JUNE 1, 1989
<u>CERTIFICATE OF SURVEY</u> NOT RECORDED	ROGER J. STECKER, #30103	FOUND 1" PIPE	JULY 11, 1991

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-4 1/4 CORNER
FOUND 1" IRON PIPE IN OPEN FIELD. VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF ABOVE CERTIFICATE OF SURVEY AND L.C.R.C.

FOUND WITNESSES
 L. 4687, P. 432 N.20°E. 8.97' PK. NAIL IN WEST FACE OF 12" OAK
 SOUTH 7.15' PK. NAIL IN EAST FACE OF 8" MAPLE
 S.30°W. 28.34' PK. NAIL IN EAST FACE OF 22" HICKORY

FIELD MEASUREMENTS AND RECORDED DISTANCES
 I-4 TO I-3 2681.39' (M.) 2640.00' G.L.O. (R.)
 I-4 TO I-5 2689.91' (M.) 2640.00' G.L.O. (R.)



Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-4 T.3N., R.14E. I REPLACED 1" IRON PIPE WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408".

WITNESSES
 N.34°E. 8.97' FOUND PK IN WEST FACE OF 12" OAK
 S.75°E. 18.16' FOUND PK IN EAST FACE OF 14" ASH
 S.07°E. 7.15' FOUND PK IN EAST FACE OF 8" MAPLE
 S.35°W. 28.34' FOUND PK IN EAST FACE OF 22" HICKORY

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-18-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Recorded by Steven E. Dunn Date Nov. 9, 1994
 Surveyor's Michigan License No. 28408