

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located in: Chesterfield

Corner Code # I-6

RECORDED IN MACOMB COUNTY

RECORDS AT: 8:30 A M.

DEC 28 1993

Signature of Clerk - Registrar of Deeds

CLERK - REGISTRAR OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 3 N R 14 E I-6
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

- 4. Lot No. , Recorded Plat
5. Private Claims

I, Steven E. Dunn, in a field survey on October 24, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13. A dot is marked at the intersection of column I and row 6.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Post - No evidence of original corner found.

GLO Original survey performed by Preston 2-18-1818.

Plats: L.67, P.7-10 Birchgrove Subdivision.

L.C.R.C.: L.6000, P.955 Martin C. Dunn #30081 September 7, 1993

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-6 1/4 Corner.

Found Iron Rod. Verified location by comparing distance along West line of above plat North to Section corner and checking witness ties of above L.C.R.C.

Replaced with Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. Signed by Frank J. DeDecker, PS PE, CHAIRMAN.



C. Description of monument for corner and accessories established to perpetuate localizing the position of the corner:

I-6 T.3N.,R.14E.

Macomb County Monument Marker #28408 on 3/4" X 24" Iron Rod.

Witnesses:

- North - 66.50' Found PK nail in East face of utility pole.
West - 76.55' Found PK nail in South face of utility pole.
East - 1.84' Found PK nail in North face of utility pole.
N.86°E. - 50.44' Found 1/2" Iron Rod with traverse cap #30081.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn

Date 12-20-93

Surveyor's Michigan License No. 28408