

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C152292

94 DEC 14 AM 10:56

CADRE
RECORD
MICHIGAN
COUNTY
NEEDS
MI

LIBER 6527 PAGE 869

Register of Deeds Stamp & File Number

corners in

MACOMB Located In: **CHESTERFIELD** Corner Code # _____
(County)

Public Land Survey T 3N R 14E I-7 _____
T _____ R _____
T _____ R _____
T _____ R _____

Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		6		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	18		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

STEVEN E. DUNN, in a field survey on APRIL 4, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND
GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

CERTIFICATE OF SURVEY
L. 2336 P. 453-454 WILLIAM E. SODERBERG, #17635 FOUND 1/2" IRON ROD IN MONUMENT BOX OCTOBER 20, 1972

L.C.R.C.	NAME AND NUMBER	DESCRIPTION	DATE
L. 2302 P. 918	ROBERT L. SMITH, #16052	FOUND 1" PIN IN MONUMENT BOX	JULY 7, 1972
L. 4687 P. 327	MARTIN C. DUNN, #30081	FOUND 1/2" IRON ROD IN MONUMENT BOX	JULY 21, 1989
L. 5158 P. 890	FRANK J. DEDECKER, #8386	FOUND 1/2" IRON ROD IN MONUMENT BOX	JULY 25, 1991

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-7 SECTION CORNER
FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT. VERIFIED LOCATION BY COMPARING FOUND WITNESS TIES OF ABOVE L.C.R.C.'s AND COMPARED M-DOT DISTANCES TO THE SECTION CORNERS TO THE EAST AND WEST.

FOUND WITNESS TIES
L. 5158, P. 890
AZ 18° 49.92' CUT "+" IN NORTH RIM OF SANITARY MANHOLE
AZ 42° 163.35' PK NAIL IN NORTHWEST FACE OF UTILITY POLE
AZ 279° 182.83' CUT "+" ON TOP OF FIRE HYDRANT CENTERLINE NUT
AZ 348° 34.45' FORM NAIL IN EAST FACE OF UTILITY POLE

FIELD MEASUREMENTS AND RECORDED DISTANCES
I-7 TO H-7 2714.42' (M.) 2714.46' (R.) M.D.O.T.
I-7 TO J-7 2690.20' (M.) 2690.12' (R.) M.D.O.T.
I-7 TO I-6 2686.40' (M.)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-7 T.3N., R.14E. I REPLACED 1/2" IRON ROD WITH 3/4" x 24" IRON ROD WITH 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT MI. ACT 345 #28408" IN MONUMENT BOX.

WITNESSES
AZ 18° 49.92' FOUND CUT "+" IN NORTH RIM OF SANITARY MANHOLE
AZ 42° 163.35' FOUND PK NAIL IN NORTHWEST FACE OF UTILITY POLE
AZ 279° 182.83' FOUND CUT "+" ON TOP OF FIRE HYDRANT CENTERLINE NUT
AZ 348° 34.45' FOUND FORM NAIL IN EAST FACE OF UTILITY POLE

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10-18-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN



THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

signed by Steven E. Dunn Date Nov. 9, 1994
Surveyor's Michigan License No. 28408