

**SURVEY &  
REMONUMENTATION**

APR 28 1995

C104893

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

94 AUG -5 PM 1:41

CARMELLA KABAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

For corners in

<b>MACOMB</b> (County)	Located In: <b>CHESTERFIELD</b>	Corner Code # <b>J-7</b>
1. Public Land Survey	T <u>3N</u> R <u>14E</u>	<u>J-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

LIBER 06415PC469

Register of Deeds Stamp & File Number

I, STEVEN E. DUNN, in a field survey on APRIL 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
6												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

SHEET 1 OF 2

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO POST - NO EVIDENCE OF ORIGINAL CORNER FOUND

GLO ORIGINAL SURVEY PERFORMED BY PRESTON 2-18-1818

**CERTIFICATE OF SURVEY**

- L. 2279 P. 663 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, APRIL 20, 1972
- L. 2327 P. 139 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, SEPTEMBER 21, 1972
- L. 2327 P. 140 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, SEPTEMBER 21, 1972
- L. 2327 P. 141 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, SEPTEMBER 21, 1972
- L. 2327 P. 142 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, SEPTEMBER 21, 1972
- L. 2336 P. 399 - ROBERT L. SMITH, #16052, FOUND 1" IRON ROD IN MONUMENT BOX, APRIL 20, 1972
- L. 2339 P. 105 - GEORGE A. CIEMOCHOWSKI, #13577, FOUND METAL BOX, OCTOBER 30, 1972
- L. 2898 P. 504 - ROBERT L. SMITH, #16052, JANUARY 4, 1978
- L. 5969 P. 154 - DONALD H. KING, #30085, FOUND IRON IN MONUMENT BOX, AUGUST 11, 1993

**B. Description of corner-evidence found and/or method applied in restoring or reestablishing corner:**

J-7 1/4 CORNER

FOUND 1/2" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT.  
 VERIFIED LOCATION BY COMPARING FOUND WITNESSES OF L.C.R.C.'s L.4132, P. 922 AND L. 5158, P. 890. COMPARED M-DOT L. 4132 P. 622 N.W. 103.60 TO M.S.H.D. REFERENCE TAG IN EAST FACE OF UTILITY POLE  
 N.W. 80.67 TO M.S.H.D. REFERENCE TAG IN NORTHEAST FACE OF UTILITY POLE  
 L. 4687 P. 327 N.20°W. 103.62, FOUND PK. NAIL & M.S.H.D. WASHER IN EAST FACE OF UTILITY POLE  
 L. 5158 P. 890 AZ. 54° 60.70, CUT + IN CENTER OF MBT MANHOLE  
 AZ. 177° 84.50, PK. NAIL W/SDA TAG IN EAST FACE OF UTILITY POLE  
 AZ. 215° 86.80, CENTERLINE TOP OF NUT ON HYDRANT  
 AZ. 295° 80.77, PK. NAIL W/MSHD TAG IN NORTHEAST FACE OF UTILITY POLE  
 AZ. 343° 103.53, PK. NAIL W/MSHD TAG IN NORTHEAST FACE OF UTILITY POLE  
 DISTANCE WEST TO SECTION CORNER AND DISTANCE EAST TO SECTION CORNER AS SHOWN ON CERTIFICATE OF SURVEY, L. 5969 P. 154.  
 DISTANCE J-7 TO I-7 = 2690.20' M                      DISTANCE J-7 TO K-7 = 2619.68' M

REPLACED WITH MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

J-7 T.3N., R.14E. MACOMB COUNTY MONUMENT MARKER STAMPED WITH P.S.#28408 ON 3/4" x 24" IRON ROD IN MONUMENT BOX IN CONCRETE PAVEMENT.

**WITNESSES**

- N54°E 60.70' FOUND "X" SCRIBED IN NORTH RIM OF SANITARY MANHOLE.
- S03°E 84.50' FOUND P.K. NAIL W/SDA TAG IN EAST FACE OF UTILITY POLE.
- S35°W 86.80' FOUND TOP CENTER NUT OF FIRE HYDRANT.
- N65°W 80.77' FOUND P.K. NAIL WITH MSHD TAG IN NORTH EAST FACE OF UTILITY POLE.
- N17°W 103.53' FOUND P.K. NAIL WITH MSHD TAG IN NORTH EAST FACE OF UTILITY POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER

Signed by Steven E. Dunn

Date July 22, 1994

Surveyor's Michigan License No. 28408



ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 348 OF 1980 AT A MEETING HELD ON 6-21-94  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

L.C.R.C.

- L. 2302 P. 918 - ROBERT L. SMITH, #16052, FOUND 1" PIN IN MONUMENT BOX, JULY 7, 1972
- L. 4132 P. 922 - JOHN R. FENN, #23505, FOUND 5/8" REROD IN MONUMENT BOX, SEPTEMBER 10, 1987
- L. 4687 P. 327 - MARTIN C. DUNN, #30081, FOUND 1/2" IRON ROD IN MONUMENT BOX, JULY 21, 1989
- L. 5158 P. 890 - FRANK J. DEDECKER, #8386, FOUND 1/2" IRON ROD IN MONUMENT BOX, JULY 25, 1991