

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for County (Macomb), Located In (Chesterfield), Corner Code (# K-5), and numbered sections 1-5 for Public Land Survey, Property Controlling, Miscellaneous, and Private Claims.

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Cassella Asanoff, Clerk - Register of Deeds, Macomb County, Michigan. Register of Deeds Stamp & File Number

I, Steven E. Dunn, in a field survey on December 8, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column J and row 5.

A. Description of original monument and accessories and/or subsequent restoration:
GLO Post - No Evidence of Original Corner.
GLO Original survey performed by Preston 2-18-1818.

Certificate of Survey - Unrecorded Martin C. Dunn #30081 June 6, 1989

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
K-5 Found 1/2" Iron Rod. Verified location by Plats.
L.15, P.42 - A.P. #10
L.15, P.40 - A.P. #9

Replaced with Macomb County Monument Marker #28408 on 3/4"x 24" Iron Rod in Monument Box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
K-5 T.3N.,R.14E.
Macomb County Monument Marker #28408 on 3/4"x 24" Iron Rod in Monument Box.
Witnesses:
N:20°W. - 23.00' Found P.K. Nail NE face of Twin 5" Maple.
S:28°W. - 27.66' Found P.K. Nail East face of 11" Pine.
N:65°E. - 45.45' Found P.K. Nail NW face of 23" Cherry.
S:54°E. - 51.15' Found P.K. Nail NE face of 30" Maple.

The selected location is a careful and faithful perpetuation of the position of the original corner.

Signed by Steven E. Dunn Date 12-21-93
Surveyor's Michigan License No. 28408

Vertical stamp: ACCEPTED BY THE MACOMB COUNTY SURVEY MEASUREMENT GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-20-93. Includes signature of Frank J. DeDecker, PS, PE, CHAIRMAN.

