

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

MACOMB

(County)

CHESTERFIELD TOWNSHIP

Located In: Corner Code #

1. Public Land Survey

T ___ R ___

#005 SURVEY & RE-MONUMENTATION

T ___ R ___

T ___ R ___

T ___ R ___

2. Property Controlling in Section

S 13 T 3 N R 14 E

MAR 17 2000

3. Miscellaneous Property in Sec.

S ___ T ___ R ___

SECTION

S ___ T ___ R ___

1091806
 LIBER 9267 PAGE 963
 12/27/1999 01:12:08 P.M.
 MACOMB COUNTY, MI
 CARMELLA SABAUGH, REG/DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims INSECT. SOUTHWESTERLY LINE

I, ROBERT H. BIRKETT, in a field survey on SEPTEMBER 8, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

INTERSECTION SOUTHWESTERLY LINE P.C. 614 WITH EAST LINE SECTION 13, CHESTERFIELD TOWNSHIP.

1817 W. PRESTON, GLO, SET WOOD POST

a) 1973, R. SMITH #16052, SET P.K. NAIL, SURVEY L. 2433, P. 35 M.C.R.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

INTERSECTION SOUTHERLY LINE P.C. 614 WITH EAST LINE SECTION 13, CHESTERFIELD TOWNSHIP.

FOUND BURIED MONUMENT BOX WITH AXLE SHAFT FROM RECORD INFORMATION AND SURVEY (a).

FIELD MEASUREMENTS

INTER. S'LY LINE P.C. 614 TO INTER. N.W. LINE P.C. 614

G.L.O. (1818) - NOT MEASURED

R. SMITH (1973) CALCULATED - 3445.86'

RE-MONUMENTATION (1999) - 3445.11'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

INTERSECTION SOUTHWESTERLY LINE P.C. 614 WITH EAST LINE SECTION 13, CHESTERFIELD TOWNSHIP. SET A 3/4" IRON WITH A 2" DIAMETER ALUMINUM CAP STAMPED "MACOMB COUNTY MONUMENT, M1 ACT 345, #41094, P.C.C." IN RAISED MONUMENT BOX

20° - 74.21' - SET P.K. NAIL W/REMON TAG IN N.W. FACE UTILITY POLE W/DROPS.

155° - 72.68' - SET CHISELED "+" ON WEST RIM STORM MANHOLE.


240° - 19.63' - SET CHISELED "+" ON EAST RIM SANITARY MAN HOLE.

320° - 51.85' - SET P.K. NAIL W/REMON TAG IN EAST FACE TELEPHONE POLE.

THE SELECTED LOCATION IS ACCEPTED BY ME AND IS GENERALLY ACCEPTED BY PROFESSIONAL SURVEYORS AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 10/5/99

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



Signed by Robert H. Birkett Date November 23, 1999

Surveyor's Michigan License No. 41094