

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Washington Township
 Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>12E</u> | <u>A-1</u> |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| | T _____ | R _____ | _____ |
| 2. Property Controlling in Section | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
| 3. Miscellaneous Property in Sec. | S _____ | T _____ | R _____ |
| | S _____ | T _____ | R _____ |
4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION

OCT 19 1998

SECTION

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1	●												
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on April 24, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 12" White Oak S70°E 23 Links; 12" Black Oak N79°W 19 Links
 1.) 1979-Verba, PS #13603; LCRC L.3074, Pg.5 - Fnd a PK Nail
 2.) 1986-Avey, PS #15396; Survey L.05510, Pg.247 - Fnd a PK Nail
 3.) 1993-Ward, PS #22445; Unrecorded LCRC - Fnd a PK Nail

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1998-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a Monument Box located in the existing centerline of 32 Mills Road extending to the North & South, which has a bituminous surface and the existing centerline of Dequindre Road extending to the North & South, which has a gravel surface. This corner is common to M-13 (T5N, R11E), M-1 (T4N, R11E) & A-13 (T5N, R12E).

Witnesses from LCRC #1, Survey #2 & unrecorded LCRC #3 were used to recover and verify the location of the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a existing Monument Box

I accepted the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a existing Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENT BETWEEN

A-1 to A-2
 No GLO
 2991.84 Ft. (GPS-GROUND)

A-1 to B-1
 No GLO
 2738.14 Ft. (GPS-GROUND)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 07/20/98

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 A-1 I accepted the found 5/8" x 24" Iron Rod w/2" diameter brass cap stamped Oakland County Remonumentation, PS #22445 in a existing Monument Box
 N38°W 58.89' Set Mag Nail & Remon Washer NE face Power Pole
 N27°E 54.57' Set Mag Nail & Remon Washer NW face Power Pole
 S23°E 60.27' Set Mag Nail & Remon Washer SW face Power Pole
 S73°W 141.67' Set Mag Nail & Remon Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 7-2-98

