

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located in: Washington Township Corner Code #

1. Public Land Survey

T 4N R 12E B-9

2. Property Controlling in Section

T
T
T
T
S
S
S
S

3. Miscellaneous Property in Sec.

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6/29/1999

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on March 29, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 40" Black Oak S24°W 1.30 Chains; 30" White Oak N36°E 63 Links
- 1974-Gladstone, PS #19831; LCRC L.2528, Pg.499 - Fnd a 1/2" Iron in a Monument Box
 - 1978-Buckerfield, PS #10868; LCRC L.3044, Pg.604 - Fnd a 1/2" Bar in a Monument Box, used same wit as 1974 LCRC
 - 1995-Wright, PS #40165; LCRC L.6832, Pg.276 - Fnd a 1/2" Bar in a Monument Box
 - 1971-Avey, PS #15396; Survey L.2252, Pg.226 - Fnd a 1/2" Iron Bar in a Monument Box, used same wit as 1995 LCRC
 - 1977-Avey, PS #15396; Survey L.2865, Pg.252 - Object found not stated, no witnesses
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod in a Monument Box located 2.5 feet East of the existing centerline of Mt. Vernon Road extending North & South, which has a bituminous surface, and in the existing centerline of 28 Mile Road extending to the West, which has a gravel surface, and to the East, which has a bituminous surface.

Witnesses from LCRC #1, 2, 3 & 4 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.
 I accepted the found 1/2" Iron Rod in a Monument Box as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

B-9 to A-9

GLO = 40.71 chains or 2686.86 Ft.
 No recorded distances
 2688.41 Ft. (MEA 1999)

B-9 to C-9

GLO = 40 chains or 2640.00 Ft.
 Survey recorded in Liber 2252, page 226 = 2447.98 Ft.
 Survey recorded in Liber 2865, page 252 = 2646.38 Ft.
 "EYSTER'S MT. VERNON FARMS" = 2647.09 Ft.
 2646.49 Ft. (MEA 1999)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 B-9 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County"
 Monument MI Act #345", PS #17623 in a existing Monument Box
 N57°W 40.95' Set Mag Nail & Remon Washer SW face Guide Pole
 N21°E 118.85' Set Mag Nail & Remon Washer West face Power Pole
 S66°E 91.42' Set Mag Nail & Remon Washer SE face Power Pole
 S74°W 116.28' Set Mag Nail & Remon Washer North face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 7-5-99

