

SURVEY & REMONUMENTATION

APR 28 1995

C126144

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SEP 30 AM 8:59

For corners in

Washington

Macomb

(County)

Located In: Township Corner Code #

CAROL A. BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

1. Public Land Survey	T	4N	R	12E	B-13
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T	R	
	S		T	R	
3. Miscellaneous Property in Sec.	S		T	R	
	S		T	R	

06464PC457

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on July 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post; 36" White Oak N31°E 33 Links; 36" White Oak S65°W 53 Links
1.) 1994-Coulter, P.S. #14760; LCRC L.6214, Pg.307 - Set Railroad Spike

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON August 16, 1994.
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd Railroad Spike 4' North of the centerline of 26 Mile Road, which has a gravel surface. The North 1/4 corner of Section 6, T3N, R12E, is 120.73' to the East.

Witnesses from LCRC #1 were used to recover and verify the location of the found Railroad Spike.

FIELD MEASUREMENT BETWEEN

- B-13 to C-13 2640.76 Feet
- B-13 to A-13 2661.31 Feet
- C-13 to A-13 5302.07 Feet
- C-13 to A-13 5302.99 Feet Measurement taken from horizontal control map for Stoney Creek Area Park

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13 I replaced the found Railroad Spike with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".
N11°W 27.57' Set PK & Remon. Washer East face 32" Oak
N82°W 68.66' Set PK & Remon. Washer South face 20" Oak
S24°E 45.88' Set PK & Remon. Washer NE face 9" Hickory
S46°W 80.67' Set PK & Remon. Washer NW face 26" Hickory

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date August

