

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: Washington Township	Corner Code # C-1
1. Public Land Survey	T <u>4NR</u> R <u>12E</u>	<u>C-1</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 4/7, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post 10" White Oak S69°E 44 Links; 18" White Oak S08°W 110 Links  
 1.) 1977-Kobs, PS #14097; LCRC L.2765, Pg.543 - Fnd 1/2" Iron Bar in pavement  
 2.) 1976-Kobs, PS #14097; Survey L.2765, Pg.536 - Fnd 1/2" Iron Bar, used same wit as 1977 LCRC  
 3.) 1976-Kobs, PS #14097; Survey L.2765, Pg.538 - Fnd 1/2" Iron Bar, used same wit as 1977 LCRC  
 4.) 1984-Kobs, PS #14097; Survey L.3705, Pg.99 - Fnd 1/2" Iron Bar, used same wit as 1977 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod .70 feet below the surface and 2.47 feet North of the existi centerline of 32 Mile Road extending to the East & West, which has a bituminous surface. A tree-fence row extending to the South The corner as recovered is 0.37 feet South of the township line. I found a 3/8" Iron Pipe 133.52 feet to the West, which is bei used and accepted as a common corner for Sections 31 & 32, T5N, R12E, Bruce Twp., (C-13).

Witnesses from LCRC #1 were used to recover and verify the location of the found 1/2" Iron Rod.

See back side of LCRC for Field Measurements

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
 GRUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
 PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
 ON JULY 10, 1997

William E. Soderberg

WILLIAM E. SODERBERG, P.S. CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" in a new monument B on the township line  
 Due South 42.56' Set PK & Remon Washer West face 13" Maple  
 N68°E 199.14' Set PK & Remon Washer SE face 24" Walnut  
 S61°W 164.52' NE corner of house #3924  
 N47°W 183.58' Set PK & Remon Washer NE face Power Pole  
 West 133.52 feet, corner common to Sections 31 & 32, T5N, R12E, Bruce Township (C-13)



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]  
 Surveyor's Michigan License No. 17623

Date 7-16-97

769

C0561137 LIBER:07589 PAGE:435 09:21A 08/13/1997  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

FIELD MEASUREMENTS BETWEEN

C-1 to B-1

No GLO  
Survey dated 7/76, L.2765, Pg.536 = 2678.71 Ft.  
Survey dated 8/76, L.2765, Pg.538 = 2678.71 Ft.  
GRID-MEA = 2678.68 Ft.

C-1 to C-13

GLO = 1.90 chains or 125.40 Ft.  
GROUND-MEA = 133.52 Ft.

C-1 to D-1

No GLO  
GRID-MEA = 2715.00 Ft.