

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb  
(County)

Located in: Washington Township Corner Code #

- |                                    |             |              |             |
|------------------------------------|-------------|--------------|-------------|
| 1. Public Land Survey              | <u>T 4N</u> | <u>R 12E</u> | <u>C-2</u>  |
|                                    | <u>T</u>    | <u>R</u>     | <u>    </u> |
|                                    | <u>T</u>    | <u>R</u>     | <u>    </u> |
|                                    | <u>T</u>    | <u>R</u>     | <u>    </u> |
| 2. Property Controlling in Section | <u>S</u>    | <u>T</u>     | <u>R</u>    |
|                                    | <u>S</u>    | <u>T</u>     | <u>R</u>    |
| 3. Miscellaneous Property in Sec.  | <u>S</u>    | <u>T</u>     | <u>R</u>    |
|                                    | <u>S</u>    | <u>T</u>     | <u>R</u>    |

**SURVEY & REMONUMENTATION**

OCT 19 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_ Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

C0738445 LIBER:08156 PAGE:809 09:45A 07/20/1998  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

I, Huston K. Kennedy, in a field survey on February 10, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	●	5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, ~~and in this case the Macomb County Surveyor~~ GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 07/30/98

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 12" White Oak S14°W 53 Links; 30" Black Oak N13°E 92 Links  
1.) 1997-Avey, PS #30076; LCRC L.7426, Pg.202 - Fnd 1/2" Bar #14097  
2.) 1976-Kobs, PS #14097; Survey L.2723, Pg.862 - Fnd Iron Bar  
3.) 1984-Kobs, PS #14097; Survey L.3705, Pg.99 - Fnd Iron Bar, used same wit as 1984 Survey
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1998-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod and is 0.40 feet below the surface with an tree, fence & rock row extending to the North, South, East & West.

Witnesses from LCRC #1, Survey #2 were used to recover and verify the location of the found 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

**FIELD MEASUREMENTS BETWEEN**

C-2 to C-1  
GLO = 46.74 chains or 3084.84 Ft.  
Survey recorded in Liber 3705, page 99 = 3033.71 Ft.  
3033.92 Ft. (GPS-GROUND)

C-2 to C-3  
GLO = 40 chains or 2640.00 Ft.  
Survey recorded in Liber 2723, page 852 = 2650.60 Ft.  
2650.98 Ft. (GPS-GROUND)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-2 I replaced the found 1/2" Iron Rod with a 4" diameter Concrete Monument with 1/2" Iron Rod 36" long w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345" 17623  
Due South 39.02' Set Mag Nail & Remon Washer West face 12" Cherry  
S27°W 6.09' Set Mag Nail & Remon Washer SE face 14" Apple  
S42°E 23.67' Set Mag Nail & Remon Washer NE face 8" Cherry  
S87°E 37.22' Set Mag Nail & Remon Washer South face 27" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date 7-2-98

