

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb Located In: Corner Code #
 (County) Washington Township

1. Public Land Survey T 4N R 12E C-4
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

SURVEY &
 REMONUMENTATION

OCT 19 1998

SECTION

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6	5	4	3	2	1						
3													
4		7	●	8	9	10	11	12					
5													
6		18	17	16	15	14	13						
7													
8		19	20	21	22	23	24						
9													
10		30	29	28	27	26	25						
11													
12		31	32	33	34	35	36						
13													

C0738446 LIBER:08156 PAGE:810 09:45A 07/20/1998
 CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS

I, Huston K. Kennedy, in a field survey on February 11, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 10" Tamarack N64°E 383 chains
 1.) 1997-Wright, PS #40165; LCRC L.7454, Pg.909 - Fnd 3/4" Bar
 2.) AEW Engineers field notes - Fnd 1" Pipe
 3.) 1997-Wright, PS #40165; Unrecorded Survey - Fnd 3/4" Bar, used same wit as 1997 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1998-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 3/4" Iron Rod at the surface and located 8 feet North of the existing centerline of a two track dirt trail extending to the East & West, also 110 feet North of Detroit Edison Trans Line.

Witnesses from LCRC #1 were used to recover and verify the location of the found 3/4" Iron Rod.


I accepted the found 3/4" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

C-4 to C-3
 GLO = 40 chains or 2640.00 Ft.
 Unrecorded Survey by Jeffrey A. Wright, PS #40165 = 2639.43 Ft.
 From drawing (sources unknown) = 2637.33 Ft.
 2639.69 Ft. (GPS-GROUND)

C-4 to C-5
 GLO = 40 chains or 2640.00 Ft.
 From drawing (sources unknown) = 2704.19 Ft.
 2674.79 Ft. (GPS-GROUND)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-4 I replaced the found 3/4" Iron Rod with a 4" diameter Concrete Monument with 1/2" Iron Rod 36" H x 36" W / 2" diameter aluminum cap stamped Macomb County Monument, MI Act #345" #17623
 S73°W 217.32' Set Mag Nail & Remon Washer North face Power Pole
 S65°W 199.30' NE leg at concrete base of Detroit Edison Tower #9529
 N69°W 29.64' Set Mag Nail & Remon Washer North face 11" Willow
 S66°E 59.86' Set Mag Nail & Remon Washer NE face Power Pole

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1890 AT A MEETING HELD ON 6/20/98

 WILLIAM E. SODERBERG, P.S., CHAIRMAN



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: 
 Surveyor's Michigan License No. 17623

Date 7-2-98