

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located in: Washington Township
 Corner Code #

- | | | | |
|------------------------------------|-------------|--------------|------------|
| 1. Public Land Survey | T <u>4N</u> | R <u>12E</u> | C <u>6</u> |
| | T | R | |
| | T | R | |
| | T | R | |
| 2. Property Controlling in Section | S | T | R |
| | S | T | R |
| 3. Miscellaneous Property in Sec. | S | T | R |
| | S | T | R |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 10" White Oak S70°E 19 Links; 16" White Oak S80°W 88 Links
 1.) 1972-Kobs, PS #14097; LCRC L.2302, Pg.168 - Fnd a 1/2" Iron Bar in a Monument Box
 2.) 1992-Avey, PS #30076; LCRC L.5290, Pg.296 - Fnd a 1/2" Bar
 3.) 1972-Kobs, PS #14097; Survey L.2302, Pg.153 - Fnd a 1/2" Iron Bar in a Monument Box, used same wit as 1972 LCRC
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 1/2" Iron Rod 3 feet South of the existing centerline of Inwood Road extending to the East & West, which has a gravel surface, also a old fence, tree & rock row extending to the South.

Witnesses from LCRC #1,2 & Survey #3 were used to recover and verify the location of the found a 1/2" Iron Rod.

I accepted the found 1/2" Iron Rod as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN

C-6 to C-5
 GLO = 40 chains or 2640.00 Ft.
 Survey recorded in Liber 2302, page 153 = 2701.77 Ft.
 2701.46 Ft. (MEA 1999)

C-6 to C-7
 GLO = 40 chains or 2640.00 Ft.
 No recorded distances
 2609.92 Ft. (MEA 1999)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 C-6 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 Due North 49.85' Set Mag Nail & Remon Washer West face 21" Walnut
 S68°E 149.30' Set Mag Nail & Remon Washer North face 24" Oak
 Due South 97.19' Set Mag Nail & Remon Washer East face 18" Oak
 S56°W 100.24' Set Mag Nail & Remon Washer NW face fence post

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature] Date 7-31-99
 Surveyor's Michigan License No. 17623

901