

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located in: Washington Township	Corner Code # C-7
1. Public Land Survey	T 4N R 12E	C-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Huston K. Kennedy, in a field survey on April 15, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:  
1817-GLO Wampler, D.S.; Set Post 8" White Oak S88°W 59 Links; 10" Black Oak S84°E 47 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 3" diameter steel corner fence post with a 6' high chain link fence extending to the North & East. A old fence, tree & rock row extending to the West. I set a reference monument 6.35 feet to the West on the line between Sections 18 & 19. I could find no other evidence to dispute the location of this corner.

**FIELD MEASUREMENTS BETWEEN**

C-7 to B-7  
 GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2653.46 Ft. (MEA 1999)

C-7 to C-8  
 GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2659.67 Ft. (MEA 1999)

C-7 to C-6  
 GLO = 40 chains or 2640.00 Ft.  
 No recorded distances  
 2609.92 Ft. (MEA 1999)

C-7 to D-7  
 GLO = 40.80 chains or 2692.80 Ft.  
 No recorded distances  
 2665.23 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
C-7 I accepted the found 3" diameter steel corner fence post, I set a reference monument (4" diameter Concrete Monument with a 1/2" Iron Rod 36" long) 6.35 feet to the West. (See back side for witnesses for the reference monument).

**Witnesses to D-7**

N08°W 35.44' Set Mag Nail & Remon Washer East face 6" Elm  
 Due North 17.91' Set Mag Nail & Remon Washer West face 5" Elm  
 Due West 41.24' Set Mag Nail & Remon Washer North face 8" Elm  
 S86°E 35.80' Set Mag Nail & Remon Washer North face 5" Ash  
 West 6.35' 4" diameter Concrete Monument with a 1/2" Iron Rod 36" long

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 6/27/99  
William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]  
 Surveyor's Michigan License No. 17623

Date 7-5-99

**Town 5 North, Range 12 East, Washington Township (C-7)**

**Witnesses to the Northeast Reference Monument**

N06°E 18.60' Set Mag Nail & Remon Washer West face 5" Elm  
N03°W 33.90' Set Mag Nail & Remon Washer East face 6" Elm  
Due West 34.85' Set Mag Nail & Remon Washer North face 8" Elm  
S87°E 42.30' Set Mag Nail & Remon Washer North face 5" Ash  
East 6.35' 3" diameter Steel Corner Fence Post (D-7)

C1005088 LIBER:08988 PAGE:772 09:51A 07/20/1999  
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS