


LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: Washington Township	Corner Code # C-8
1. Public Land Survey	T <u>4N</u> R <u>12E</u>	<u>C-8</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99

 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on April 11, 1999 hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 36" Black Oak S57°E 10 Links; 8" White Oak N61°W 70 Links
 1.) 1971-Avey, PS #15396; Survey L.2252, Pg.226 - Set a 1/2" capped Iron Rod, no witnesses
 2.) 1977-Kobs, PS #14097; Survey L.2811, Pg.753 - Fnd a 1/2" Iron Bar w/cap #15396
 3.) 1977-Avey, PS #15396; Survey L.2865, Pg.252 - Object found not stated, no witnesses
 4.) 1986-Kobs, PS #14097; Survey L.4055, Pg.658 - Fnd 1/2" Iron Bar w/cap #15396, used same wit as 1977 Survey
 5.) 1973-"MT. VERNON VILLAGE SUBDIVISION NO. 1", Liber 64, Pages 17-19
 6.) 1975-"MT. VERNON VILLAGE SUBDIVISION NO. 2", Liber 66, Pages 4-7
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd a 4" Concrete Monument located 1.30 feet South and 1.00 feet West of a 2-1/2" diameter Chain Link Steel Fence Post. A fence-free row extending to the East, West & South.

Witnesses from Survey #1 & 3 were used to recover and verify the location of the found 4" Concrete Monument.

I accepted the found 4" Concrete Monument as the best evidence of the original corner position.

FIELD MEASUREMENTS BETWEEN


C-8 to C-7
 GLO = 40 chains or 2640.00 Ft.
 No recorded distances
 2659.67 Ft. (MEA 1999)

C-8 to C-9
 GLO = 40 chains or 2640.00 Ft.
 Survey recorded in Liber 2865, page 252 = 2650.93 Ft.
 "MT. VERNON VILLAGE SUBDIVISION NO. 2" = 2650.93 Ft.
 2650.21 Ft. (MEA 1999)



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner
 C-8 | accepted the found 4" Concrete Monument with a 1/2" Iron Rod and placed a 2" diameter aluminum monument stamped "Macomb County Monument, MI Act #345", PS #17623
 N40°W 26.68' Set Mag Nail & Remon Washer SW face 7" Cherry
 S04°E 37.92' Set Mag Nail & Remon Washer NE face 38" Twin Cherry
 S84°E 29.60' Set Mag Nail & Remon Washer South face 31" Twin Cherry
 N63°E 23.50' Set Mag Nail & Remon Washer SE face 9" Apple

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: 
 Surveyor's Michigan License No. 17623

Date 8-5-99

203