

LIBER 06166P016

B999623

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Washington Twp.

Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Clerk - Register of Deeds Macomb County, Michigan

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 N R 12 E C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at row 12, column C.

I, Huston K. Kennedy, in a field survey on December 14, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set post; 12" Black Oak N35° E 73 Lns; 12" White Oak S54° W 97 Lns. The corner was recovered based upon coordinates as provided by the Huron-Clinton Metropolitan Park Authority.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Nothing was found at the corner. No witnesses were existing. A chiseled cross was set located 1.5'± South of the centerline of 26 Mile Road, which is concrete surface.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: C-13 I replaced the set chiseled cross with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box. N08°W-76.77 ft- Set PK & Remon. tag East face Power Pole N47°W-44.27 ft-Set PK & Remon. tag SW face 32" Oak S44°E-36.70 ft-Set PK & Remon. tag SW face 51" Oak S74°W-82.28 ft-Set PK & Remon. tag SE face 31" Oak

The selected location is a careful and faithful re-establishment of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12/14/93

