

LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: Washington Township	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>12E</u>	<u>D-1</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

SURVEY &  
 REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on 4/17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5		4		3		2		1	
3													
4	7			8		9		10		11		12	
5													
6	18			17		16		15		14		13	
7													
8	19			20		21		22		23		24	
9													
10	30			29		28		27		26		25	
11													
12	31			32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; No Post set
- 1.) 1976-Kobs, PS #14097; LCRC L.2663, Pg.159 - Set 1/2" Iron Bar & Cap No. 14097
- 2.) 1989-Kobs, PS #14097; LCRC L.4621, Pg.466 - Fnd 1/2" Iron
- 3.) 1976-Kobs, PS #14097; Survey L.2663, Pg.157 - Fnd 1/2" Iron Bar, used same wit as 1976 LCRC

ACCEPTED BY THE MACOMB COUNTY SURVEY PEEI GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON April 10, 1997

William E. Soderberg  
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd 1/2" Iron Rod 5" below the surface 1.0 feet North of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface. The corner as recovered is 0.87 feet North of the township line. I found a 1/2" Iron Rod 191.28 feet West, which is being used and accepted as the South 1/4 corner of Section 32, T5N, R12E, Bruce Twp., (D-13).

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Rod.

See back side of LCRC for Field Measurements

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-1 I replaced the found 1/2" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI AC 345" #17623 in a new Monument Box on the township line  
 S54°E 104.40' Set PK & Remon Washer NE face 37" Willow  
 S38°W 48.56' Set PK & Remon Washer NW face 14" Maple  
 N52°E 143.44' Set PK & Remon Washer SE face Power Pole  
 S15°E 64.36' NW corner of house #4900  
 West 191.28 feet, South 1/4 corner of Section 32, T5N, R12E, Bruce Twp., (D-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy  
 Surveyor's Michigan License No. 17623

Date 7-16-97



770

FIELD MEASUREMENTS BETWEEN

D-1 to C-1

No GLO  
GRID-MEA = 2715.00 Ft.

D-1 to D-13

No GLO  
GROUND-MEA = 191.28 Ft.

D-1 to E-1

No GLO  
Survey dated 3/4/76, L.2663, Pg.157 = 2790.58 Ft.  
GRID-MEA = 2790.35 Ft.