

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Macomb</u> (County)	Located In: Washington Township	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>12E</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on May, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		19		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 44" White Oak N08°E 6 Links; 22" Ash S67°W 6 Links
 1955 "CHEROKEE HILLS", Liber 34, page 5
 19 "CHEROKEE HILLS NO. 1" Liber , page
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner as recovered is 2 feet South of the existing centerline of 28 Mile Road extending to the East & West, which has a bituminous surface, and 270 feet ± East of the centerline of a bridge.

HOW THE CORNER WAS RECOVERED

The North line of "CHEROKEE HILL NO. 1" was held based upon the existing monumentation as found, and the corner was set at the distance from E-9 based upon the coordinates from the Horizontal Control Map for Stoney Creek Area.

FIELD MEASUREMENTS BETWEEN

D-9 to E-9
 GLO = 40.80 chains or 2692.80 Ft.
 No recorded distances
 2669.84 Ft. (Horizontal Control Map for Stoney Creek Area)
 2670.56 (MEA 1999)

D-9 to C-9
 GLO = 40.80 chains or 2692.80 Ft.
 No recorded distances
 2722.50 Ft. (Horizontal Control Map for Stoney Creek Area)
 2717.04 (MEA 1999)

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-9 I set a 1/2" x 24" Iron Rod with a 2" diameter aluminum cap stamped "Macomb County Mosurfer, MI Act #328
 #17623 in a new Monument Box
 S56°W 72.50' Set Mag Nail & Remon Washer NW face Power Pole
 N32°W 30.65' Set Mag Nail & Remon Washer Top of Guard Rail Post
 N32°E 27.85' Set Mag Nail & Remon Washer Top of Guard Rail Post
 S37°E 23.25' Set Mag Nail & Remon Washer Top of Guard Rail Post



The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature] Date 8-5-99
 Surveyor's Michigan License No. 17623

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99
[Signature]
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

909