

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb
 (County)

Located In: Washington Township Corner Code #

1. Public Land Survey

T 4N R 12E D-11

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous Property in Sec.

S _____ T _____ R _____

4. Lot No. _____ Recorded Plat _____
 5. Private Claims _____

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7						8			9			10
5													
6	10						17			16			15
7													
8	19						20			21			22
9													
10	30						29			28			27
11													
12	31						32			33			34
13													

I, Huston K. Kennedy, in a field survey on April, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 30" Black Oak S26°E 32 Links; 14" White Oak N10°E 55 Links
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1999-Kennedy Surveying, Inc. - Kennedy, PS #17623 - The monumentation as found at the Northeast corner and the Northwest corner of "LOCKWOOD SUBDIVISION" was held and used as the line between Sections 29 & 32 per the plat of "LOCKWOOD SUBDIVISION". This plat also depicts the intersection of the North-South 1/4 line with the North line of Section 32. The distance along the North line of Section 32 from the Northwest of Lot 8 to this intersection of the North-South 1/4 line is 241.2 feet and the corner was set at this distance. The corner as set is 5 feet South of a new 5' chain link fence extending to the East & West.

FIELD MEASUREMENTS BETWEEN

D-11 to C-11
 GLO = 40.34 chains or 2662.44 Ft.
 No recorded distances
 2712.54 Ft. (MEA 1999)

D-11 to E-11
 GLO = 40.34 chains or 2662.44 Ft.
 "LOCKWOOD SUBDIVISION" = 2638.80 Ft.
 2638.80 Ft. (MEA 1999)

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-27-99
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN



- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 D-11 | set a 4" diameter Concrete Monument with a 1/2" x 36" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act #345", PS #17623
 S56°W42.20' Set Mag Nail & Remon Washer NW face 26" Twin Oak
 S23°E 32.22' Set Mag Nail & Remon Washer NE face 10" Pine
 S72°E 33.00' Set Mag Nail & Remon Washer North face 23" Cherry
 S18°W 39.52' Set Mag Nail & Remon Washer SW face 10" Pine

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by: [Signature]
 Surveyor's Michigan License No. 17623

Date 7-29-99