

**SURVEY &
REMONUMENTATION**

APR 28 1995

C152192

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6527 PAGE 769

94 DEC 14 AM 10:50
CARR
REGISTERED DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

or corners in _____
Macomb (County)
 Located In: Washington Twp. Corner Code #

Public Land Survey	T <u>4N</u> R <u>12E</u>	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Huston K. Kennedy a field survey on September 10, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 17-GLO Wampler, D.S.; Set Post; 16" White Oak N88°E 65 Links; 15" Black Oak N77°W 1.90 Links
- 1983-Kobs, P.S. #14097; LCRC L.3532, Pg.264 - Fnd 1/2" Pipe
- 1986-Kobs, P.S. #14097; Survey L.3900, Pg.803 - Fnd 1/2" Pipe
- 1993-Kobs, P.S. #14097; Survey L.5831, Pg.257 - Fnd 1/2" Pipe, used same wit as 1986 Survey
- 1993-Kobs, P.S. #14097; Survey L.5969, Pg.150 - Fnd 1/2" Pipe, used same wit as 1986 Survey

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe 3" deep 1.7 feet East of the centerline of Mound Road, which has a bituminous surface, and 16 feet South of the centerline of 30 Mile Road, which has a gravel surface and extends to the East. There is a tree-fence line extending to the West.

Witnesses from LCRC #1 and Survey #2 were used to recover and verify the location of the found 1/2" Iron Pipe.

FIELD MEASUREMENT BETWEEN

E-5 to F-5 2689.32 Feet
 E-5 to E-6 2631.49 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94

William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I replaced the found 1/2" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a new Monument Box.
- S45°W 64.30' Set PK & Remon. Washer SE face 14" Pine
- S81°W 38.67' Set PK & Remon. Washer South face 13" Box Elder
- N50°E 57.53' Set PK & Remon. Washer SE face Power Pole
- S58°E 26.48' Set PK & Remon. Washer NE face 15" Box Elder

selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the location of the original corner.



ad by Huston K. Kennedy
 Surveyor's Michigan License No. 17623

Date September 20, 1994