

SURVEY & REMONUMENTATION

C126146

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
Washington

94-SEP 30 AM 9:00

COMMISSION

For corners in
Macomb
(County)

Located In: Township Corner Code #

CARMELLA BAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

LIBER 06464PC459

Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>4N</u>	R	<u>12E</u>	<u>E-10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		
	S		T		
3. Miscellaneous Property in Sec.	S		T		
	S		T		

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	13		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO, D.S.; Set Post 26" Black Oak S14*E 47 Links; 8" White Oak N16*E 39 Links
1.) 1975-Avey, P.S. #15396; Survey L.2642, Pg.743 - Fnd 1/2" Bar in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod w/cap #300?? 1' West of the centerline of Mound Road, which is a bituminous surface.

Witness from above mentioned recorded survey were used to recover and verify the location of the found 1/2" Iron Rod w/cap #300??.

FIELD MEASUREMENT BETWEEN

E-10 to E-9 2712.48 Feet
E-10 to E-11 2623.62 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON AUGUST 16, 1994.
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
E-10 I replaced the found 1/2" Iron Rod w/cap #300?? with 3/4" X 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a new Monument Box.
N51°E 21.26' Set PK & Remon. Washer NW face 10" Ash
N46°W 43.57' Set PK & Remon. Washer NE face 23" Hickory
S33°E 42.89' Set PK & Remon. Washer West face twin 15" Cherry
S17°E 97.26' Set PK & Remon. Washer West face 30" Ash

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by [Signature]
Surveyor's Michigan License No. 17623

Date August 27