

LIBEA 06166PC066

B998673

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

For corners in

Form with fields for County (Macomb), Located In (Washington Twp.), Corner Code (# E-11), and numbered sections 1-5 for survey types.

DEC 28 1993

Signature of Clerk - Registered of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

I, Huston K. Kennedy, in a field survey on December 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13, containing numbers 1-36 and a central dot at row 11, column D.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set post; 10" Black Oak S72°W 63 Lnks; 20" Black Oak S40°E 34 Lnks
1974-Avey, P.S. #15396; Survey L.2467, Pg.824 - Fnd 3/4" pipe in a monument box.
1988-Kobs, P.S. #14097; Survey L.4375, Pg.715 - Fnd 1/2" pipe in a monument box.
1988-Kobs, P.S. #14097; LCRC L.4375, Pg.726 - Same wits as 1988 survey
1989-Kobs, P.S. #14097; Survey L.4621, Pg.437 - Same wits as 1988 survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 -Fnd a PK Nail located in the centerline of Mound Road, which is bituminous surface.

Two witness points from the 1988 LCRC were found and they were used to recover and verify the PK Nail as the location of the section corner. The PK Nail was extracted and a monument box which was located in the centerline of Mound Road, 16" beneath the surface. There is a fence line extending to the West.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93.
Signature: Frank J. DeDecker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.
E-11 I replaced the found PK Nail with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S31°W-43.19 ft-Set PK & Remon. tag SE face Twin 8" Ash
N86°W-38.77 ft-Set PK & Remon. tag above existing witness South face Fence Post
N23°E-45.66-Set PK & Remon. tag NW face 27" Oak
S82°E-21.55 ft-Set PK & Remon. tag North face 32" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature]
Surveyor's Michigan License No. 17623

Date 12/16/93

