

LIBER 061668018

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

11999631

For corners in

Macomb (County)

Located In: Washington Twp.

Corner Code #

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Lorraine A. ... CLERK - REGISTER OF DEEDS MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

Table with 3 columns: Survey Type (Public Land Survey, Property Controlling in Section, Miscellaneous Property in Sec.), Corner Code (T, S), and Range (4, 12, E-12).

4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 20" White Oak N51°W 74 Lnks; 36" White Oak S62°E 1.98 Lnks
1976-Kobs, P.S. #14097; Survey L.2663, Pg.155 - Fnd 1/2" Iron Rod in a Monument Box
1976-Kobs, P.S. #14097; LCRC L.2663, Pg.160 - Same wits as 1976 Survey
1977-Fenn, P.S. #23505; LCRC L.2882, Pg.365 - Fnd 1/2" Iron Rod
1978-Soderberg, P.S. #17635; Survey L.2902, Pg.555-556 - Same wits as 1977 LCRC
1979-Smith, P.S. #16052; LCRC L.3168, Pg.942 - Set 1/2" Iron Rod
1979-Smith, P.S. #16052; Survey L.3169, Pg.27 - Same wits as 1979 LCRC
1980-Soderberg, P.S. #17635; Survey L.3218, Pg.63 - Same wits as 1977 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a monument box located 5' West of the centerline of Mound Road, which is bituminous surface. A PK Nail was found that is located 3.4'± North and 3'± West of the Section corner.

Three witness points from the 1977 LCRC above were found and they were used to recover and verify the found 5/8" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93. FRANK J. DeDECKER, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

- E-12 I replaced the found 5/8" Iron Rod in a monument box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S12°E-141.08 ft-Set PK Nail & Remon. tag SW face Power Pole
S51°E-59.55 ft-Set PK Nail & Remon. tag NE face 21" Pine
S88°E-30.80 ft-Set PK Nail & Remon. tag South face Power Pole
N63°W-69.35 ft-Set PK Nail & Remon. tag SW face 13" Pine

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-10-93



Grid table with columns A-M and rows 2-13. Cell 12,33 contains a black dot.