

LIBER 06166PG019

R999632

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED IN MACOMB COUNTY
RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk/Register of Deeds
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

For corners in
Macomb

(County)

Located In: Washington Twp.
Corner Code -# E-13

- 1. Public Land Survey T 4 R 12 E-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. A dot is marked at row 13, column C.

Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 22" White Oak N80°E 77 Lnks; 34" Black Oak S10°E 91 Lnks
1976-Kobs, P.S. #14097; Survey L.2663, Pg.155 - Fnd 1/2" Iron Rod in a monument box.
1976-Kobs, P.S. #14097; LCRC L.2663, Pg.160 - Same wits as 1976 Survey
1977-Fenn, P.S. #23505; LCRC L.2882, Pg.365 - Fnd 1/2" Iron Rod in a monument box.
1978-Soderberg, P.S. #17635; Survey L.2902, Pg.555-556 - Fnd 1/2" Iron Rod in a monument box.
1980-Soderberg, P.S. #17635; Survey L.3218, Pg.63 - Same wits as 1978 Survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a monument box that is 4' West of the centerline of Mound Road which is bituminous surface and 80'+ North of the centerline of the westbound lane of 26 Mile Road, which is concrete surface.

Three witness points from the 1977 LCRC were found and they were used to recover and verify the found 1/2" Iron Rod in a monument box.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93
Signature of Frank J. DeDecker, P.S., PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate location of corner:

- E-13 I replaced the found 1/2" Iron Rod in a monument box with a 3/4" x 24" Iron Rod-w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a monument box.
S88°W-50.30'-Set PK Nail & Remon. tag above existing witness in South face Power Pole
N58°E-27.65'-Top of bottom row of masonry blocks at bend in cemetery wall
N83°E-70.33'-Set PK Nail & Remon. tag in South face Power Pole
S21°E-119.83'-Set PK Nail & Remon. tag in West face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date 12-10-93

