

**SURVEY &
REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

<u>Macomb</u> (County)	Located In: Washington Township	Corner Code # F-1
1. Public Land Survey	T 4N R 12E	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEE GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/97

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 5/8, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Post not set
- 1.) 1977-Kobs, PS #14097; LCRC L.2882, Pg.478 - Fnd 1/2" Iron Bar
- 2.) 1990-Avey, PS #30076; LCRC L.4983, Pg.761 - Fnd P.K. Nail
- 3.) 1975-Kobs, PS #14097; Survey L.2590, Pg.332 - Object found not stated, no witnesses
- 4.) 1977-Kobs, PS #14097; Survey L.2882, Pg.430 - Fnd 1/2" Iron Bar, used same wit as 1977 LCRC
- 5.) 1977-Kobs, PS #14097; Survey L.4220, Pg.445 - Fnd 1/2" Iron Bar, used same wit as 1977 LCRC
- 6.) 1990-James, PS # ; Survey, L.4947, Pg.329 - Fnd P.K. Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - The corner has since been perpetuated with 1/2" Iron Rod 2" below the surface and 2 feet South of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface. The corner as recovered is 0.67 feet South of the township line. Found a 1/2" Iron which is being used and accepted as the South 1/4 corner of Section 33, T5N, R12E, Bruce Township (F-13), which is located 360.14 feet to the West.

Witnesses from LCRC #2 were used to recover and verify the location of the corner.

See back side of LCRC for Field Measurements

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" #17623 in a new Monument Box on the township line
 Due South 26.42' Set PK & Remon Washer WEST face 32" Oak West 69.23 feet found 1/2" Iron Rod
 S43°E 54.48' Set PK & Remon Washer NE face 27" Elm South 60.09 feet found 1/2" Iron Rod
 N66°E 64.98' Set PK & Remon Washer SE face 36" Oak
 N63°W 114.16' Set PK & Remon Washer SW face 26" Oak
 West 360.14 feet, South 1/4 corner of Section 33, T5N, R12E, Bruce Twp., (F-13)

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence position of the original corner.

Signed by *H. Kennedy*
 Surveyor's Michigan License No. 17623

Date 8-8-97



9x ✓

771

FIELD MEASUREMENTS BETWEEN

F-1 to E-1

No GLO

Survey dated 5/19/77, L.2882, Pg. 430 = 2595.31 Ft.

GPS-MEA = 2664.50 Ft. or GROUND CAL. = 2664.74 Ft.

F-1 to F-13

No GLO

GPS-MEA = 360.11 Ft. or GROUND CAL. = 360.14 Ft.

F-1 to G-1

No GLO

GPS-MEA = 2666.77 Ft. or GROUND CAL. = 2667.01 Ft.

*C0568788 LIBER:07613 PAGE:799 10:28A 09/02/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS*