

# SURVEY & REMONUMENTATION

APR 28 1995

C152194

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 6527 PAGE 771

94 DEC 14 AM 10:50  
CAROL BAUGH  
REGISTERED DEEDS  
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

or corners in \_\_\_\_\_

Macomb \_\_\_\_\_ Located In: Washington Corner Code # \_\_\_\_\_  
(County) Twp.

Public Land Survey	T 4N	R 12E	F-5
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
Property Controlling	S _____	T _____	R _____
in Section	S _____	T _____	R _____
Miscellaneous	S _____	T _____	R _____
Property in Sec.	S _____	T _____	R _____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Huston K. Kennedy in a field survey on September 10, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as pressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- 17-GLO Wampler, D.S.; Set Post; 42" White Oak N78°E 113 Links; 18" White Oak S07°W 81 Links
- 1986-King, P.S. #30085; LCRC L.3900, Pg.792 - Fnd 1/2" Iron Bar
- 1986-Kobs, P.S. #14097; LCRC L.3900, Pg.794 - Fnd 1/2" Pipe in a Monument Box
- 1974-Kobs, P.S. #14097; Survey L.2534, Pg.427 - Fnd 1/2" Iron Bar, used same wit as 1986 LCRC
- 1974-Kobs, P.S. #14097; Survey L.2548, Pg.960 - Fnd 1/2" Iron Bar, used same wit as 1986 LCRC
- 1975-Kobs, P.S. #14097; Survey L.2569, Pg.85 - Fnd 1/2" Iron Bar, used same wit as 1986 LCRC

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Pipe 6" deep in a Monument Box 6' South of the centerline of 30 Mile Road, which has a gravel surface, with a tree-fence row extending to the North & South. A driveway to house #6971 is 15' East of corner.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 1/2" Iron Pipe in a Monument Box.

FIELD MEASUREMENT BETWEEN

F-5 to E-5 2689.32 Feet  
F-5 to G-5 2669.73 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
ON 9-20-94

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 1/2" Iron Pipe in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum Cap. Scanned Macomb County Monument MI Act 345 #17623 in a existing Monument Box.  
S21°W 21.69' Set PK & Remon. Washer SE face 26" Cherry  
S11°E 17.33' Set PK & Remon. Washer West face 22" Cherry  
N51°W 39.91' Set PK & Remon. Washer NE face 8" Cherry  
N05°E 31.92' Set PK & Remon. Washer East face 9" Ash



selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the

ed by *H.K.* Date September 20, 1994  
Surveyor's Michigan License No. 17623