

**SURVEY &
REMONUMENTATION**

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Washington

For corners in

Macomb

(County)

Located In: Township Washington Corner Code # F-7

1. Public Land Survey	T <u>4</u> N R <u>12</u> E	<u>F-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

C105001

LIBER 06415PG478

94 AUG -5 PM 1:42

CARMELLA SABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 20" White Oak N16°E 30 Links; 14" White Oak S40°E 68 Links
- 1.) 1979-Verba, P.S. #13603; LCRC L.3074, Pg.11 - Fnd 1/2" Re-rod inside of a Monument Box.
- 2.) 1980-Kobs, P.S. #14097; LCRC L.3295, Pg.780 - Fnd 5/8" Iron Bar in a Monument Box.
- 3.) 1987-Stonerock, P.S. #13601; LCRC L.4185, Pg.91 - Fnd Monument Box.
- 4.) 1980-Kobs, P.S. #14097; Survey L.3295, Pg.766 - Fnd 5/8" Iron Bar in a Monument Box, used same wit 1980 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a Monument Box 3.8' South of the centerline of 29 Mile Road, which has a bituminous surface, and a tree & fence row extending to the North and South.

Witnesses from LCRC #1, 2 & 3 were used to recover and verify the location of the found 5/8" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

F-7 to E-7 2653.96 Feet
F-7 to G-7 2720.94 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 7-19-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- F-7 I replaced the found 5/8" Iron Rod in a Monument Box with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N05° E 33.88' Set PK & Remon. Washer West face Power Pole
- S05° W 55.65' Set PK & Remon. Washer NW face 23" Oak
- S30° W 77.56' Set PK & Remon. Washer NW face 18" Oak
- S70° W 84.38' Set PK & Remon. Washer NW face 18" Oak

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by *Huston Kennedy*
Surveyor's Michigan License No. 17623

Date July 21, 1994