

**SURVEY & REMONUMENTATION**

APR 28 1995

C126147

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Washington

Macomb

(County)

Located In: Township Corner Code #

1. Public Land Survey	T	4	N	R	12	E	F-11
	T		R				
	T		R				
	T		R				
2. Property Controlling in Section	S		T		R		
	S		T		R		
3. Miscellaneous Property in Sec.	S		T		R		
	S		T		R		

94 SEP 30 AM 9:00

CARMELLA BAUGH  
REGISTERED DEEDS  
MACOMB COUNTY, MI

118TR 06464PC460

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.; Set Post; 28" White Oak S63\*W 16 Links; 5" Black Oak N72\*E 26 Links  
1.) 1974-Avey, P.S. #15396; LCRC L.2522, Pg.275 - Fnd 3/4" Pipe  
2.) 1975-Pawlaczyk, P.S. #17632; LCRC L.2569, Pg.377 - Fnd 1" Pipe

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Pipe with a tree-fence row extending to the North, and a fence to the East at the Dog Leg right hole #12 of Glacier Club Golf Course.

Witnesses from LCRC #1 were used to recover and verify the location of the found 3/4" Iron Pipe.

FIELD MEASUREMENT BETWEEN

F-11 to E-11 2665.19 Feet  
F-11 to G-11 2788.82 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-11 I replaced the found 3/4" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623".  
Due North 8.47' Set PK & Remon. Washer West face 41" Oak  
N40°E 22.33' Set PK & Remon. Washer NW face 8" Elm  
S80°E 77.38' Set PK & Remon. Washer North face 11" Oak  
S60°E 28.87' Set PK & Remon. Washer NE face 10" Cherry

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*  
Surveyor's Michigan License No. 17623

Date \_\_\_\_\_

