

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Washington Twp.

Corner Code #F

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Signature of Clerk - Recorder of Deeds, Macomb County, Michigan

Register of Deeds Stamp & File Number

- 1. Public Land Survey T 4 N R 12 E F-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 1-13. A small circle is marked in row 10, column G.

I, Huston K. Kennedy, in a field survey on December, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set post; 24" White Oak N31°W 5 Lnks; 24" Poplar S01°E 13 Lnks 1990-Patterson, P.S. #17631; LCRC L.4899, Pg.724 - Set 1" Iron

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT OF 1990 AT A MEETING HELD 12-20-93. Frank J. DeDecker, PS, PE, CHAIRMAN

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1" Iron Pipe located 12.8' South of the South edge of the Eastbound lane of 26 Mile Road, which is concrete surface.

Witness Point from the 1990 LCRC above were found and they were used to recover and verify the found 1" Iron Pipe.

At a meeting of the Macomb County Peer Group on December 20, 1993, they decided that the corner was incorrectly set. The corner should be reset on the line between the SE corner Sec 33, T6N, R12E, and the N 1/4 corner Sec 4, T3N, R12E, extending West to intersect the N-S 1/4 as shown on a drawing provided by the MCS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: F-13 I replaced the found 1" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" N66°W-34.02 ft-Cross in station 125+00 South edge 26 Mile Road N79°E-70.14 ft-Cross in station 126+00 South edge 26 Mile Road S27°W-44.01 ft-Set PK Nail & Remon. tag in SE face (2) 12" Poplar S73°E-77.33 ft-Set PK Nail & Remon. tag in North face 12" Poplar

The selected location is a careful and faithful re-establishment of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-16-93

