

**SURVEY &
 REMONUMENTATION**

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APR 07 1998

For corners in

| | | |
|---------------------------------------|------------------------------------|---------------|
| <u>Macomb</u> (County) | Located In: Washington Township | Corner Code # |
| 1. Public Land Survey | T <u>4N</u> R <u>12E</u> | <u>G-1</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

SECTION

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8/15/97
William E. Soderberg
 WILLIAM E. SODERBERG, P.S., CHAIRMAN

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on 4/17, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| A | B | C | D | E | F | G | H | I | J | K | L | M |
| 1 | | | | | | | | | | | | |
| 2 | 6 | 5 | 4 | | | | | | | | | |
| 3 | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | |
| 5 | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | |
| 7 | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | |
| 9 | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | |
| 11 | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | |
| 13 | | | | | | | | | | | | |

- A. Description of original monument and accessories and/or subsequent restoration:
 1817-GLO Wampler, D.S.; Set Post 18" White Oak N27°W 1.71 chains; 4" White Oak S66°E 11 links
 1.) 1979-Buckerfield, PS #10868; LCRC L.3185, Pg.559 - Set a P.K. & Flasher
 2.) 1990-Avey, PS #30076; LCRC L.4983, Pg.761 - Fnd a P.K. Nail
 3.) 1995-King, PS #30085; LCRC L.6586, Pg.225 - Fnd a P.K. Nail
 4.) 1990-James, PS #19835; Survey L.4947, Pg.329 - Fnd a P.K. Nail
 5.) 1968-"HILLCREST ORCHARD SUBDIVISION", Liber 24, Page 34

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 1997 Kennedy Surveying, Inc. - Kennedy, PS #17623 - Fnd P.K. Nail 2.30 feet North of the existing centerline of 32 Mile Road extending to the East & West, which has a bituminous surface, also in the existing centerline of Campground Road extending to the South, which has a bituminous surface, and 56 feet East of the existing centerline of Campground Road extending to the North, which has a gravel surface. The corner as recovered is 0.05 feet North of the township line. Found an empty Monument Box 55.57 feet to the West which is being used and accepted as a common corner for Sections 33 & 34, T5N, R12E, Bruce Township (G-13).

Witnesses from LCRC #1, 2, 3, unrecorded Survey #4 and "HILLCREST ORCHARD SUBDIVISION" were used to recover and verify the location of the found P.K. Nail.

See back side of LCRC for Field Measurements

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 G-1 I set a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345" 17623 in a new Monument Box on the township line
 N51°E 42.87' Set PK & Remon Washer SE face 25" Maple
 N17°W 47.77' Set PK & Remon Washer SW face Guide Pole
 S40°E 38.98' Set PK & Remon Washer NE face Power Pole
 N62°W 97.27' Set PK & Remon Washer SW face Power Pole
 Due South 59.71 feet, found P.K. Nail 5.0 feet West of edge of bituminous
- 1.) West 55.58 feet corner common to Sections 33 & 34, T5N, R12E, Bruce Township (G-13)
 2.) North 0.05 feet found P.K. Nail



The selected location is accepted by me and is generally accepted by Professional Surveyors as the position of the original corner.

Signed by *H. Kennedy*
 Surveyor's Michigan License No. 17623

Date 10-21-97

738

FIELD MEASUREMENTS BETWEEN

G-1 to F-1

No GLO

GPS-MEA = 2666.77 Ft. or GROUND CAL. = 2667.01 Ft.

G-1 to G-12

GLO = 80 links or 52.80 Ft.

GPS-MEA = 55.57 Ft. or GROUND CAL. = 55.58 Ft.

G-1 to H-1

No GLO

GPS-MEA = 2622.65 Ft. or GROUND CAL. = 2622.89 Ft.

C0619500 LIBER:07769 PAGE:484 08:30A 12/12/1997
CARMELLA SABAUGH-MACOMB COUNTY, MI REG/DEEDS