

# SURVEY & REMONUMENTATION

APR 28 1995

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C152195

or corners in **COMMISSION**

Macomb (County) Located In: Washington Twp. Corner Code #/

Public Land Survey	T	4N	R	12E		G-5
	T		R			
	T		R			
	T		R			
Property Controlling in Section	S		T		R	
Miscellaneous	S		T		R	
Property in Sec.	S		T		R	

LIBER 6527 PAGE 772

94 DEC 14 AM 10:50

CARR  
REGIS  
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5							●						
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Huston K. Kennedy a field survey on September 10, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

- 17-GLO Wampler, D.S.; Set Post; 12" White Oak N16°E 32 Links; 23" Red Oak S26°W 81 Links
- 1974-Kobs, P.S. #14097; LCRC L.2534, Pg.481 - Fnd 3/4" Iron Bar in a Monument Box
- 1986-Avey, P.S. #30076; LCRC L.4080, Pg.889 - Fnd 3/4" Bar in a Monument Box
- 1989-Avey, P.S. #30076; LCRC L.4584, Pg.240 - Reset 3/4" Iron Rod based upon the witnesses recorded in Liber 4080, Page 889 of Macomb County Records.
- 1974-Kobs, P.S. #14097; Survey L.2534, Pg.427 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1974 LCRC
- 1974-Kobs, P.S. #14097; Survey L.2534, Pg.429 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1974 LCRC
- 1974-Kobs, P.S. #14097; Survey L.2534, Pg.456 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1974 LCRC
- 1974-Kobs, P.S. #14097; Survey L.2548, Pg.960 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1974 LCRC
- 1976-Kobs, P.S. #14097; Survey L.2653, Pg.41 - Fnd 3/4" Iron Bar in a Monument Box, used same wit as 1974 LCRC

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

4 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron 5" deep and 2' East of the centerline of Camp Ground Road, which has a gravel surface and 5 feet South of the centerline of 30 Mile Road, which has a gravel surface.

Witnesses from LCRC #1 & 2 were used to recover and verify the location of the found 3/4" Iron Rod.

**FIELD MEASUREMENT BETWEEN**

- G-5 to F-5 2669.73 Feet
- G-5 to H-5 2557.60 Feet
- G-5 to G-6 2611.72 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94

*William E. Soderberg*  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I replaced the 3/4" Iron Rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument, MI Act 345 #17623".

- N67°W 85.93' Set PK & Remon. Washer NE face 26" Ash
- N40°W 40.47' Set PK & Remon. Washer SW face Power Pole
- N47°E 66.02' Set PK & Remon. Washer SE face 16" Maple
- S48°E 34.47' Set PK & Remon. Washer SW face 18" Maple

selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



ed by *Huston Kennedy*  
Surveyor's Michigan License No. 17623

Date September 20, 1994