

**SURVEY &
REMONUMENTATION**

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

C152196

corners in **COMMISSION**

Macomb
(County)

Located In: Washington Corner Code #
Twp.

LIBER 6527 PAGE 773

Public Land Survey	T	<u>4N</u>	R	<u>12E</u>	<u>G-6</u>
	T		R		
	T		R		
	T		R		
Property Controlling	S		T		
in Section	S		T		
Miscellaneous	S		T		
Property in Sec.	S		T		

94 DEC 14 AM 10:50

CAMPBELL BAUGH
REGISTERED DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	13	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Huston K. Kennedy in a field survey on September 10, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the present manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

- 17-GLO Wampler, D.S.; Set Post; 14" White Oak N49°W 20 Links; 18" Black Oak S26°E 16 Links
- 1986-Avey, P.S. #30076; LCRC L.4080, Pg.889 - Fnd 1/2" Bar in 3/4" Pipe in a Monument Box
- 1976-Kobs, P.S. #14097; Survey L.2653, Pg.41 - Fnd 3/4" Pipe in a Monument Box
- 1978-Kobs, P.S. #14097; Survey L.2923, Pg.830 - Fnd 3/4" Pipe in a Monument Box, used same wit as 1976 Survey
- 1986-Kobs, P.S. #14097; Survey L.4055, Pg.607 - Fnd 3/4" Pipe in a Monument Box, used same wit as 1976 Survey

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

14-Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 3/4" Iron Pipe 2" deep in a Monument Box 2.5' East of the centerline of Camp Ground Road, which has a gravel surface. A tree, fence and rock row extending to the East & West.

Witnesses from LCRC #1 & Survey #2 were used to recover and verify the location of the found 1/2" Iron Pipe.

FIELD MEASUREMENT BETWEEN


- G-6 to G-5 2611.72 Feet
- G-6 to G-7 2672.99 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 9-20-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I replaced the found 3/4" Iron Pipe with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Michigan MI Act 345 #17623" in a existing Monument Box.
- N81°W 24.23' Set PK & Remon. Washer South face 24" Oak
- S82°W 27.22' Set PK & Remon. Washer North face 10" Ash
- N84°E 28.36' Set PK & Remon. Washer South face 27" Oak
- S77°E 31.90' Set PK & Remon. Washer SW face Guide Pole



selected location is accepted by me and is generally accepted by Professional Surveyors as the best available location of the original corner.

ed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date September 20, 1994