

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

C105004

For corners in

Washington

Macomb

Located In: Township Corner Code #

(County)

1. Public Land Survey	T	4	N	R	12	E		G-8
	T			R				
	T			R				
	T			R				
	T			R				
2. Property Controlling in Section	S			T			R	
	S			T			R	
3. Miscellaneous Property in Sec.	S			T			R	
	S			T			R	

LIBER 06415PG481

94 AUG -5 PM 1:42

CARMELLA RABAUGH
REGISTER OF DEEDS
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set Post; 28" White Oak S53°E 20 Links; 26" White Oak N66°W 80 Links
- 1.) 1990-Nelson, P.S. #21273; LCRC L.4816, Pg.947 - Fnd 5/8" Re-rod in a Monument Box
 - 2.) 1978-Kobs, P.S. #14097; Survey L.3062, Pg.533 - Fnd 5/8" Iron Bar in a Monument Box
 - 3.) 1979-Avey, P.S. #15396; Survey L.4576, Pg.649 - Fnd 1/2" Iron Bar in a Monument Box
 - 4.) 1993-King, P.S. #30085; Survey L.5969, Pg.141 - Fnd 5/8" Iron Bar in a Monument Box

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 5/8" Iron Rod in a Monument Box, 5.7' West of the centerline of Camp Ground Road, which has a bituminous surface, and a tree & fence row extending to the West, and Orchards Golf Course to the East.

Witnesses from Recorded Surveys #2, 3 & 4 were used to recover and verify the location of the found 5/8" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

- G-8 to G-7 2624.63 Feet
- G-8 to G-9 2591.21 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN
PUBLIC ACT 345 OF 1990 AT A MEETING HELD
ON 7-19-94

William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-8 I replaced the found 5/8" Iron Rod in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N86°W 26.20' Set PK & Remon. Washer NE Corner of Rock Pillar
 - N30°W 152.65' Set PK & Remon. Washer NE face Power Pole
 - N70°E 38.10' Set PK & Remon. Washer North face 8" Walnut
 - S85°E 39.02' Set PK & Remon. Washer North face 8" Walnut

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by *Huston K. Kennedy*
Surveyor's Michigan License No. 17623

Date July 21,

