

# SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

C105005

For corners in

Washington

Macomb  
(County)

Located In: Township \_\_\_\_\_ Corner Code ## \_\_\_\_\_

LIBER 06415PG482

- |                                    |   |   |   |   |    |   |     |
|------------------------------------|---|---|---|---|----|---|-----|
| 1. Public Land Survey              | T | 4 | N | R | 12 | E | G-9 |
|                                    | T |   | R |   |    |   |     |
|                                    | T |   | R |   |    |   |     |
|                                    | T |   | R |   |    |   |     |
|                                    | T |   | R |   |    |   |     |
| 2. Property Controlling in Section | S |   | T |   | R  |   |     |
|                                    | S |   | T |   | R  |   |     |
| 3. Miscellaneous Property in Sec.  | S |   | T |   | R  |   |     |
|                                    | S |   | T |   | R  |   |     |

94 AUG -5 PM 1:42

CARROLL A. BAUGH  
REGISTER OF DEEDS  
MACOMB COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Huston K. Kennedy, in a field survey on June 15, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	10	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- 1817-GLO Wampler, D.S.; Set Post; 14" Maple S04\*W 27 Links; 16" White Oak N46\*E 7 Links
- 1.) 1973-Avey, P.S. #15396; LCRC L.2426, Pg.327 - Fnd 1/2" Bar in hand hole
  - 2.) 1976-Kobs, P.S. #14097; LCRC L.2681, Pg.139 - Fnd 1/2" Iron Bar in Monument Box
  - 3.) 1982-O'Rourke, P.S. #16937; LCRC L.3450, Pg.231 - Fnd 1/2" Iron Bar in Monument Box
  - 4.) 1988-Avey, P.S. #30076; LCRC L.4353, Pg.430 - Fnd 1/2" Iron Bar in Monument Box
  - 5.) 1989-Donnelly, P.S. #21563; LCRC L.4723, Pg.604 - Fnd 1/2" Iron Bar in Monument Box
  - 6.) 1972-Avey, P.S. #30076; Survey L.2314, Pg.243 - Fnd 1/2" Pipe in hand hole
  - 7.) 1976-Kobs, P.S. #14097; Survey L.2681, Pg.126 - Same wit as 1976 LCRC
  - 8.) 1979-Kobs, P.S. #14097; Survey L.3129, Pg.155 - Same wit as 1976 LCRC
  - 9.) 1988-Kobs, P.S. #14097; Survey L.4543, Pg.150 - Same wit as 1976 LCRC

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rd in a Monument Box 4.9' West of the centerline of Camp Ground Road, which has a bituminous surface, 4' North of the centerline of 28 Mil Road, which has a bituminous surface.

Witnesses from LCRC #1, 3, 4 and 5 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

**FIELD MEASUREMENT BETWEEN**

- G-9 to H-9 2549.86 Feet
- G-9 to F-9 2688.87 Feet
- G-9 to G-8 2591.21 Feet
- G-9 to G-10 2685.02 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER  
GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN  
PUBLIC ACT 345 OF 1990 AT A MEETING HELD  
ON 7-19-94  
William E. Soderberg  
WILLIAM E. SODERBERG, P.S., CHAIRMAN

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- G-9 I replaced the found 1/2" Iron Rod in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
- N50°E 53.71' - Set PK & Remon. Washer NW face Power Pole
  - N45°W 39.22' - Set PK & Remon. Washer SW face Power Pole
  - S30°W 97.08' - Set PK & Remon. Washer East face Power Pole
  - S45°E 49.87' - Set PK & Remon. Washer NE face Power Pole

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.



Signed by Huston K. Kennedy  
Surveyor's Michigan License No. 17623

Date July 21, 1994