

**SURVEY &
REMONUMENTATION**

C126148

APR 28 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

94 SEP 30 AM 9: 00

For corners in
COMMISSION
Macomb
(County)

Washington
Located In: Township Corner Code #

CARMEL J. BAUGH
REGISTERED DEEDS
MACOMB COUNTY, MI

- | | | | | | | | |
|---------------------------------------|---|---|---|---|----|---|------|
| 1. Public Land Survey | T | 4 | N | R | 12 | E | G-10 |
| | T | | R | | | | |
| | T | | R | | | | |
| | T | | R | | | | |
| 2. Property Controlling
in Section | S | | T | | R | | |
| | S | | T | | R | | |
| 3. Miscellaneous
Property in Sec. | S | | T | | R | | |
| | S | | T | | R | | |

LIBER 06464PC461

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Huston K. Kennedy, in a field survey on June 15, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1817-GLO Wampler, D.S.; Set Post 10" Lynn S46°E 17 Links; 20" White Oak N16°E 36 Links
1.) 1973-Avey, P.S. #15396; LCRC L.2426, Pg.327 - Fnd 1/2" Bar in hand hole
2.) 1974-Avey, P.S. #15396; LCRC L.2522, Pg.273 - Same wit as 1973 LCRC
3.) 1987-Kennedy, P.S. #17623; LCRC L.4134, Pg.721 - Fnd 1/2" Iron Rod in Monument Box
4.) 1988-Avey, P.S. #30076; LCRC L.4353, Pg.430 - Fnd 1/2" Iron Rod in Monument Box
5.) 1973-Avey, P.S. #15396; Survey L.2467, Pg.821 - Same wit as 1973 LCRC

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1994 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd 1/2" Iron Rod in a Monument Box 1.7' East of the centerline of Camp Ground Road, which has a bituminous surface, and Glacier Club Golf Course to the West.

Witnesses from LCRC 1, 3 & 4 were used to recover and verify the location of the found 1/2" Iron Rod in a Monument Box.

FIELD MEASUREMENT BETWEEN

G-10 to G-9 2685.02 Feet
G-10 to G-11 2676.51 Feet

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 8-16-94
William E. Soderberg
WILLIAM E. SODERBERG, P.S., CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10 I replaced the found 1/2" Iron Rod in a Monument Box with 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345 #17623" in a existing Monument Box.
S80°E 21.64' Set PK & Remon. Washer NE face Guide Pole
S25°W 53.91' Set PK & Remon. Washer NW face Power Pole
N85°W 80.95' Set PK & Remon. Washer South face 34" Maple
N80°E 60.22' Set PK & Remon. Washer SW corner of house #60000

The selected location is accepted by and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Date _____
Surveyor's Michigan License No. 07623

