

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb (County)

Located In: Washington Twp.

Corner Code #

- 1. Public Land Survey T 4 R 12 G-11
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat
5. Private Claims

I, Huston K. Kennedy, in a field survey on December 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column G and row 11.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration: 1817-GLO Wampler, D.S.; Set post; 11" Ash S54°E 17 Lnks; 7" Ironwood S70°W 18 Lnks 1973-Avey, P.S. #15396; LCRC L.2426, Pg.327 - Fnd PK Nail 1974-Avey, P.S. #15396; Survey L.2467, Pg.820-821 - Same wits. as 1973 LCRC 1974-Avey, P.S. #15396; LCRC L.2522, Pg.273 - Same wits. as 1973 LCRC 1987-Kennedy, P.S. #17623; LCRC L.4134, Pg.721 - Set #60 Nail

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: 1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 -Fnd 1/2" Iron Rod at the intersection of the centerline of Van Dyke Road and 3' North of the centerline of 27 Mile Road to the East. Both are bituminous surface roads.

Three witness points from the 1987 LCRC were found in Power Poles. They were used to recover and verify the found 1/2" Iron Rod.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93 FRANK J. DEDCKER, PS, PE, CHAIRMAN

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11 I replaced the found 1/2" iron rod with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument HI Act 345 #17623" in a monument box. S72°W-20.70'-Set PK Nail & Remon. tag above existing witness in South face Power Pole. S13°W-138.62'-Set PK Nail & Remon. tag in SE face 32" Maple S63°E-84.53'-Set PK Nail & Remon. tag below existing witness in South face Power Pole. N33°E-52.30'-Set PK Nail & Remon. tag above existing witness in West face Power Pole.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available evidence of the position of the original corner.

Signed by [Signature] Surveyor's Michigan License No. 17623

Date 12-10-93

