

LIBER 06166 PG 021

B998634

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Macomb

(County)

Located In: Washington Twp.

Corner Code #

- 1. Public Land Survey T 4 R 12 G-12
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

RECORDED IN MACOMB COUNTY RECORDS AT: 8:30 A.M.

DEC 28 1993

Carroll A. ...
CLERK - REGISTER OF DEEDS
MACOMB COUNTY, MICHIGAN

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Huston K. Kennedy, in a field survey on December 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1817-GLO Wampler, D.S.; Set post; 17" Beech N82°W 20 Lnks; 14" Beech S83°W 8 Lnks
- 1976-Kobs, P.S. #14097; Survey L.2723, Pg.872 - Fnd PK Nail
- 1976-Kobs, P.S. #14097; LCRC L.2723, Pg.877 - Same wits as 1976 Survey
- 1977-Kobs, P.S. #14097; Survey L.2811, Pg.745 - Same wits as 1976 Survey
- 1989-Avey, P.S. #30076; LCRC L.4584, Pg.234 - Fnd PK Nail

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 Kennedy Surveying, Inc. - Kennedy, P.S. #17623 - Fnd PK Nail that is 1' West of the centerline of Van Dyke Road, which is bituminous surface.

Three witness points from the 1989 LCRC were found and they were used to recover and verify the found PK Nail.

ACCEPTED BY THE MACOMB COUNTY SURVEY PEER GROUP AS THE OFFICIAL CORNER UNDER MICHIGAN PUBLIC ACT 345 OF 1990 AT A MEETING HELD ON 12-15-93.

Frank J. Decker
FRANK J. Dedecker, PS, PE, CHAIRMAN

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- G-12 I replaced the found PK Nail with a 3/4" x 24" Iron Rod w/2" diameter aluminum cap stamped "Macomb County Monument MI Act 345. #17623" in a monument box.
- N86°W-72.20'-Set PK Nail & Remon. tag in North face 36" Maple.
- N25°W-93.53'-Set PK Nail & Remon. tag in SW face 24" Pine.
- N44°E-50.72'-Set PK Nail & Remon. tag in NW face 19" Maple.
- S58°E-46.40'-Set PK Nail & Remon. tag above existing witness in SE face Power Pole.

The selected location is accepted by me and is generally accepted by Professional Surveyors as the best available location of the position of the original corner.

Signed by Huston K. Kennedy
Surveyor's Michigan License No. 17623

Date 12-10-93

